

**SURVEY &
REMONUMENTATION**

FEB 27 1998

Ottawa County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>B-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

97 DEC -8 AM 11:28

Dan Schellton
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice J. Rosema in a field survey on Jan. 11, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-11
G.L.O. by N. Brookfield L.C.R.C. rec. in Liber 3, Page 123 on Oct. 22, 1976
in 1832 Solid iron
Set H.M.P. Nail in side 18" Ash WNW 86.56'
9" Beech S76°E 6 lks Nail in side 44" Oak WSW 179.15'
10" Walnut N39°W 25 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


B-11
Found 3/4" steel rod in gravel road. Replaced with 3/4" x 3' Steel rod with remon cap
Found nail in N side 48" Oak S82°W 179.12'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

RA. 345 OTTAWA COUNTY
PEER APPROVED 9-16-96
YDM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11
3/4" x 3' steel rod with remon cap
Set nail and remon tag in N side 48" Oak S82°W 179.12'
Set nail and remon tag in top of wood T. post S7°W 25.33'
Set nail and remon tag in S side 4" twin Maple N88°E 256.44'
Center of manhole cover S64°E 53.50'
Centerline of E-W gravel Road N 3'±



\$ 1.00 PHOTO

Signed by *Maurice J. Rosema* Date Sept. 16, 1996
Surveyor's Michigan License No. 27459