

APR 05 1996

Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	B-13
	T _____ R _____	(S $\frac{1}{4}$ cor of
	T _____ R _____	Sec. 31)
	T _____ R _____	Tallmadge Twp
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**RECORDED**

95 NOV 29 PM 1:46

*Phyllis Chittman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

**Register of Deeds Stamp & File Number**

I, Maurice J. Rosema, in a field survey on Sept. 26, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 B-13  
 GLO - 1837 (Noah Brookfield D.S.) L.C.R.C. recorded in Liber 3, Page 123  
 5" Beech N44°W 17 lks Oct. 19, 1976  
 18" Maple N82°E 60 lks Solid iron  
 Nail in side 14" Basswood N 110.94'  
 L.C.R.C. recorded in Liber 6, Nail in side fc post S 33.76'  
 Page 256 - Feb. 23, 1993 On N-S fc  
 (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 B-13  
 Found C.I. monument in monument box  
 Found PK nail in W side wood fc post S5°W 34.08'  
 Found nail in SE side 10" Ash S69°W 77.90'  
 Found nail in W side 18" Elm N12°E 40.31'  
 Found nail in E side 8" Elm N1°E 44.30'  
 Found X mark in top of plastic fc post S5°E 52.40'



I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 B-13  
 C.I. monument in monument box  
 Set nail and Ottawa Co. remon. tag in W side wood fc post S5°W 34.08'  
 Set nail and Ottawa Co. remon. tag in SE side 10" Ash (5' high) S69°W 77.90'  
 Set nail and Ottawa Co. remon. tag in W side 18" Elm N12°E 40.31'  
 Set nail and Ottawa Co. remon. tag in E side 8" Elm N1°E 44.30'  
 X mark in top of plastic fc post - S5°E 52.40'  
 On c/l E-W bit. conc. road  
 ON brush and tree row N and S

**P.A. 345 OTTAWA COUNTY**  
**PEER APPROVED** 11-20-95

Signed by Maurice J. Rosema Date October 18, 1995  
 Surveyor's Michigan License No. 27459

B-13, T7N, R13W

L.C.R.C. recorded in Liber 6, Page 256 - Feb. 23, 1993

Cast monument

16-D E. side 8" Elm

N10°W 44.36'

Double hd N and T in NW side 18" Elm

N10°E 40.42'

X mark on c/l top plastic fc post

S35°E 65.78'

PK nail in W side wood post

S 34.04'

Double hd nail in SE side 10" Ash (5' high

S60°W 77.93'

4 11.00 CORNER