

APR 05 1996

Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Ottawa (County) Located In: Corner Code #  
 1. Public Land Survey T T7N R R13W C-7  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_ (SE cor of  
 T \_\_\_\_\_ R \_\_\_\_\_ Section 18)  
 T \_\_\_\_\_ R \_\_\_\_\_ Tallmadge Twp  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

RECORDED

95 NOV 15 PM 2:07

*R. J. Hillman*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

Maurice J. Rosema in a field survey on Dec. 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-7  
 GLO - 1832 (Lucius Lyon D.S.) L.C.R.C. recorded in Liber 3,  
 9" Beech S9°E 12 lks Page 188 - Sept. 19, 1977  
 16" Maple N62°W 9 lks (over)

L.C.R.C. recorded in Liber 5,  
 Page 207 - April 8, 1985  
 (over)

RA. 345 OTTAWA COUNTY  
 PEER APPROVED 10/23/95

*M. D. Nedwoda*  
*MDN*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7  
 Found C.I. monument  
 Found nail in S side wood post at tele. box W 74.39



I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7  
 C.I. monument  
 Set nail and Ottawa Co. remon. tag in S side wood post at tele. box N81°W 74.39'  
 Set nail and Ottawa Co. remon. tag in E side 8" Elm N21°W 33.12'  
 Set nail and Ottawa Co. remon. tag in NW side 8" tw Elm N17°E 25.41'  
 Set nail and Ottawa Co. remon. tag in SW side 7" Elm S60°E 33.68'  
 c/l gravel road (on curve) SW 34'  
 On tree row to W

Signed by *M. J. Rosema* Date October 19, 1995  
 Surveyor's Michigan License No. 27459

C-7 T7N, R13W

L.C.R.C. recorded in Liber 5, Page 207 - April 8, 1995

C.I. monument

Nail in N side 8" Elm	NWS 39.70'
Nail in E side 4" Maple	NNE 27.51'
Nail in SW side 8" Elm	SE 28.99'
Nail in S side wood post at tele. box	W 74.38'

L.C.R.C. recorded in Liber 3, Page 188 - Sept. 19, 1977

C.I. monument

4" Chinese Elm	SE 27.65'
6" Chinese Elm	E 21.58'
5" Chinese Elm	ENE 19.84'
5" Chinese Elm	N 39.30'

\$ 11.00 CORNER