

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 15 AM 11:53

For corners in
Ottawa
 (County)

Dorothy K. Hartman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	D-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Maurice J.
 Rosema
 Nov. 26 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5		●											
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 D-5

GLO - 1838 by Rosema - 1985 per Joiner - 1991 per
 R. Whitcomb L.C.R.C. L.C.R.C.
 Set post (over) (over)
 6" Ironwood - S30°W .2 ch.
 24" Elm - N47°E .14 ch.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 D-5

Found C.I. mon.
 Found nail in E. side 10" Apple - N1°E 90.28'
 Found nail in SW. side 8" Elm - N12°E 91.97'
 Found P.K. nail in NE. side wood fence post - N63°W 78.73'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

RA. 345 OTTAWA COUNTY
 PEER APPROVED 12/12/94
Arday D. Newell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 D-5

C.I. mon.
 Set nail and remon. tag in W. side 16" Apple clump - N0°E 89.52'
 Set nail and remon. tag in W. side 8" Elm - N12°E 91.97'
 Set nail and remon. tag in NE. side 12" Elm - N49°W 77.70'
 Set nail and remon. tag in NE. side 10" W. Cherry - N35°W 73.80'
 Set nail and remon. tag in NE. side tri. 6" W. Cherry - N65°W 85.53'
 Set nail in N. side 6" W. Cherry - N87°W 118.04'



Dec. 10, 1994

Signed by *Maurice J. Rosema* Date _____
 Surveyor's Michigan License No. 27459

Part A - continued

Rosema - 1985 per L.C.R.C.

3/4" iron

Nail in E. side 8" Apple (at top of bank) - N. 90.45'

Nail in NE. side 8" Elm (at top of bank) - NW. 77.08'

Nail in S. side 8" Elm (at top of bank) - W. 115.28'

Centerline of Leonard Street - S. 779.97'

Joiner - 1991 per L.C.R.C.

C.I. mon.

10" Apple clump - N. 90.46'

12" Elm - NW. 77.09'

P.K. nail in fence post - NW. 78.83'

6" Elm - NE. 91.85'

CONF # 3800
NUMBER
CONF # 4000
1550