

**SURVEY &
REMONUMENTATION**

Ottawa County Remonumentation

APR 05 1995 **CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970
COMMISSION

For corners in

<u>Ottawa</u> (County)	Located in:	Corner Code ##
1. Public Land Survey	T <u>T7N</u> R <u>R13W</u>	D-13
	T _____ R _____	(S $\frac{1}{4}$ cor. of
	T _____ R _____	Sec. 32
	T _____ R _____	Tallmadge Twp
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

95 NOV 29 PM 1:46

Edythe K. Kellerman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Maurice J. Rosema, in a field survey on Oct. 16, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-13

GLO - 1837 (Noah Brookfield D.S.)	L.C.R.C. recorded in Liber 6,
26" W Oak N83°E 57 lks	Page 176 - Oct. 10, 1991
9" Beech N37°W 43 lks	(over)

L.C.R.C. recorded in Liber 4,	L.C.R.C. recorded in Liber 1,
Page 19 - Oct. 10, 1979	Page 821 - Nov. 17, 1972
(recorded as D-1, T6N, R13W)	(over)
(over)	

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11-20-95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-13

Found C.I. monument	
Found nail in S side 20" Oak	N72°E 24.70'
Found nail in W side 10" Basswood clump	N12°E 15.58'
Found nail in S side 12" Ash	N84°W 30.61'
Found nail in SW side 6" Hickory	S23°E 24.54'

Edythe K. Kellerman



I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-13

C.I. monument	
Set nail and Ottawa Co. remon. tag in S side 20" Oak	N72°E 24.70'
Set nail and Ottawa Co. remon. tag in W side 10" Basswood clump	N12°E 15.58'
Set nail and Ottawa Co. remon. tag in E side 13" Ash	N47°W 31.35'
Set nail and Ottawa Co. remon. tag in S side 12" Ash	N86°W 30.61'
Set nail and Ottawa Co. remon. tag in SW side 9" Hickory	S23°E 24.54'
Centerline of creek	W 36'±
On N-S barbed wire fc	

Signed by Maurice J. Rosema Date Oct. 19, 1995
Surveyor's Michigan License No. 27459

D-13, T7N, R13W

L.C.R.C. recorded in Liber 4, Page 19 - Oct. 10, 1979
(recorded as D-1, T6N, R13W)

6" Basswood clump	N 15.6'
16" Oak	ENE 24.2'
8" Basswood	WNW 30.5'

L.C.R.C. recorded in Liber 6, Page 176 - Oct. 10, 1991

C.I. monument

9" Hickory	SSE 24.52'
12" Ash	W 30.58'
19" Oak	ENE 24.88'
10" Basswood	N 15.61'

L.C.R.C. recorded in Liber 1, Page 821 - Nov. 17, 1972

T-post

Nail in side 9" Hickory	SSE 24.6'
Nail in side 6" Ash	W 30.57'
Nail in side 10" Bass in clump	N 15.54'
Nail in side 16" Oak	ENE 24.16'

\$ 11.00 CORNER