

SURVEY & REMONUMENTATION

JUN 28 1999

Ottawa County Remonumentation

RECORDED

98 NOV -4 PM 2:30

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

[Signature]
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In:		Corner Code #
	7N	13W	E-2
1. Public Land Survey	T___ R___	_____	W 1/4, cor. Sec. 4 Tallmadge Township
	T___ R___	_____	_____
	T___ R___	_____	_____
	T___ R___	_____	_____
2. Property Controlling in Section	S___ T___ R___	_____	_____
	S___ T___ R___	_____	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____	_____
	S___ T___ R___	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice J. Rosema, in a field survey on Oct. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5	●	4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	10			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-2
GLO - 1838 by Whitcomb
Set post
20" Beech - S37°E 4 links
18" Sugar - N24.5°W 49 links
- LCRC rec. Liber 6, Page 92
(1990 - Joiner)
C.I. mon.
Power pole - WNW 29.34'
28" Willow - SW 74.18'
7" Maple - SE 39.59'
- Guy pole - NE 28.50'
6" Ash - NNE 62.63'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-2
Found C.I. mon. in centerline of N-S gravel road 0.8' below grade
Found nail in SE side tri 5" Ash - NE 62.62'
Found nail in S side Power pole - ENE 28.58'

I hereby accept the C.I. mon. as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-2
C.I. mon.
Set nail and remon. tag in SE side tri 5" Ash - N23°E 62.62'
Set nail and remon. tag in S side Power pole - N73°E 28.58'
Set nail and remon. tag in W side 7" Maple - S37°E 39.10'
Set nail and remon. tag in S side Power pole - N66°W 29.31'
Set nail and remon. tag in NW side 28" Willow - S40°W 74.24'

10/19/98
[Signature]

STATE OF MICHIGAN
MAURICE J. ROSEMA
LAND SURVEYOR
NO. 27459
LICENSED PROFESSIONAL SURVEYOR

Receipt #18213
\$1.00 PHOTO
\$9.00 CORNER

Signed by *[Signature]*
Surveyor's Michigan License No. 27459

Date Oct. 17, 1998