

# SURVEY & REMONUMENTATION

APR 24 1995

## COMMISSION

### Ottawa County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:53

*D. J. ...*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
Ottawa

(County)

Located In:

Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>7N</u> R <u>13W</u> | <u>E-7</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

Maurice J.  
Rosema

I, \_\_\_\_\_, in a field survey on Oct. 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- |                            |                               |
|----------------------------|-------------------------------|
| E-7                        |                               |
| GLO - 1838 by              | Greer - 1973 per L.C.R.C.     |
| R. Whitcomb D.S.           | rec. in L. 2, P. 147 (over)   |
| 36" W. Oak - S25 E .24 ch. | Nederveld - 1974 per L.C.R.C. |
| 8" Beech - S68 W .24 ch.   | rec. in L. 2, P. 667 (over)   |
|                            | VanOrder - 1978 per L.C.R.C.  |
|                            | rec. in L. 3, P. 301          |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- E-7  
Found C.I. mon. 0.6' below grade  
Found nail in S. side 14" Hickory - N2°E 49.73'  
Found nail in side of 10" (dead) W. Cherry - S27°W 27.28'  
Found nail in E. side 10" (dead) W. Cherry - S34°E 23.02'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94  
*Kendry D. Nederveld*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-7  
C.I. mon.  
Set nail and remon. tag in E. side 10" (dead) W. Cherry - S34°E 23.02'  
Set nail and remon. tag in S. side 14" Hickory - N2°E 49.73'  
Set nail and remon. tag in NW. side tw. 6" tree - N16°E 7.09'  
Set nail and remon. tag in E. side tw. 7" Maple - N58°W 27.82'



Signed by *Maurice J. Rosema*

Date Dec. 10, 1994

Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

