

**SURVEY &
REMONUMENTATION**

Ottawa County Remonumentation
APR 05 1996 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
COMMISSION

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R13W</u>	E-9
	T _____ R _____	(SE cor of
	T _____ R _____	Section 20)
	T _____ R _____	Tallmadge Twp
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

95 NOV 15 PM 2:07

Polystia Kullsvand
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Maurice J. Rosema, in a field survey on Dec. 31, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 E-9

GLO - 1832 (R. Whitcomb D.S.)	L.C.R.C. recorded in Liber 2,
14" Beech S16°E 27 lks	Page 605 - July 3, 1974
12" Maple N28°W 18 lks	(over)
L.C.R.C. recorded in Liber 5,	L.C.R.C. recorded in Liber 2,
Page 68 - July 22, 1983	Page 147 - May 8, 1973
(over)	(over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9
 Found C.I. monument
 Found nail in E side 14" Elm NNW 9.15'
 Found nail in E side 14" Elm NNE 26.98'
 Fc post SSE 0.71'



I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9
 C.I. monument
 Set nail and Ottawa Co. remon. tag in W side 7" wood post S17°E 1.00'
 Set nail and Ottawa Co. remon. tag in E side 14" Elm N22°W 9.15'
 Set nail and Ottawa Co. remon. tag in E side 14" Elm N18°E 26.98'
 Set nail and Ottawa Co. remon. tag in NE side 8" Cherry N60°W 16.61'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 10/23/95

Signed by Maurice J. Rosema Date Oct. 19, 1995
 Surveyor's Michigan License No. 27459

E-9 T7N, R13W

L.C.R.C. recorded in Liber 2, Page 147 - May 8, 1973

Iron Pipe	
30" dead Elm	E 25.29'
Fc post	S 0.70'
12" Locust	N20°W 8.82'
10" Locust	N10°E 26.52'

L.C.R.C. recorded in Liber 2, Page 605 - July 3, 1974

3/4" pipe in monument box	
6" Cherry	N60°W 42.29'
10" Elm	N25°W 8.86'
10" Elm	N15°E 26.56'
30" Elm stump	E 25.2'

L.C.R.C. recorded in Liber 5, Page 68 - July 22, 1983

Iron pipe in monument box	
18" Elm	NNE 26.51'
Fc post face	S 0.70'
8" Cherry	NW 42.27'
14" Elm	NNW 8.77'

11-00
CORNER