

**SURVEY &
REMONUMENTATION**

APR 05 1996 Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
COMMISSIONING Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R13W</u>	<u>E 10</u>
	T _____ R _____	(E 1/2 cor of
	T _____ R _____	Section 29)
	T _____ R _____	Tallmadge Twp
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
95 NOV 15 PM 2:07

Phyllis Kaddman
**REGISTER OF DEEDS
OTTAWA COUNTY, MI**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					

I, Maurice J. Rosema, in a field survey on Oct. 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-10

GLO - 1832 (R. Whitcomb D.S.)
8" Ironwood S51°E 8 lks
8" Ironwood S86°W 24lks

L.C.R.C. recorded in Liber 4,
Page 65 - April 8, 1980
(over)

L.C.R.C. recorded in Liber 6,
Page 174 - October 10, 1991
(over)

L.C.R.C. recorded in Liber 1,
Page 213 - December 27, 1971
(over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10

Found C.I. Monument

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10

C.I. monument

Set nail and Ottawa County remon. tag in N side 10" Walnut
Set nail and Ottawa County remon. tag on top of conc. wall
Set nail and Ottawa County remon. tag on top of conc. wall
Set nail and Ottawa County remon. tag in S side 9" Walnut
c/l E-W gravel road
tree row to S

S77°E 131.76'
N47°E 99.15'
N25°E 75.15'
N87°E 221.73'
N 6'
E 3'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 10/23/95

Signed by Maurice J. Rosema Date October 21, 1995
Surveyor's Michigan License No. 27459

E-10, T7N, R13W

L.C.R.C. recorded in Liber 1, Page 213
- December 27, 1971

Stone

30" Maple

Steel fc post

Steel fc post

Centerline road

S50°W 24.90'

N20°W 24.5'

N55°E 40.5'

N0°E 4'

L.C.R.C. recorded in Liber 4, Page 65
- April 8, 1980

Monument box

Nail in side 10" Walnut

c/l gravel road

Iron at c/l Linden Drive

ESE 70.15'

N 4'

W 717.74'

L.C.R.C. recorded in Liber 6, Page 174
- October 10, 1991

C.I. monument

Iron in c/l Linden Drive

W edge of conc wing wall

E edge of conc wing wall

10" Walnut

W 117.73'

NE 74.85'

NE 100.16'

ESE 131.81'

\$ 11.00 CORNER