

**SURVEY &
MONUMENTATION**

Ottawa County Remonumentation
APR 05 1996 LAND CORNER RECORDATION CERTIFICATE
 COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	F-7
	T _____ R _____	(Si cor of
	T _____ R _____	Sec. 16)
	T _____ R _____	Tallmadge Twp
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

95 NOV 29 PM 1:37

Phyllis Chalmers
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Maurice J. Rosema, in a field survey on Sept. 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:
 F-7

GLO - 1838 (R. Whitcomb D.S.)	L.C.R.C. recorded in Liber 2, Page 607 - July 3, 1974.
16" Maple N 18 lks	Pinched pipe in monument box
14" Lym S18°E 28 lks	20" Maple N70°E 64.23'
	Pinched pipe S 33.60'
	18" tw Cherry N65°W 42.56'
	11" Ash N05°W 27.17'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 F-7

Found pinched pipe in monument box, replaced with 3/4" X 2' steel rod with Ottawa County remon cap

PA. 345 OTTAWA COUNTY

PEER APPROVED 11/20/95

Peer Approved Signature

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 F-7

3/4" X 2' steel rod with Ottawa County remon. cap in monument box	
Set nail and Ottawa County remon. tag in SW side 11" Poplar	N50°W 61.75'
Set nail and Ottawa County remon. tag in E side P pole	N2°W 35.00'
Set nail and Ottawa County remon. tag in N side 7" Elm	S66°E 77.68'
Set nail and Ottawa County remon. tag in top of wood post	N78°E 60.00'
Capped re-rod	S0°E 33.22'

Signed by Maurice J. Rosema Date October 21, 1995
 Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, REVISED MAY 14, REVISED JAN.,