

SURVEY & REMONUMENTATION

Ottawa County Remonumentation

RECORDED

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 15 AM 11:51

COMMISSION

For corners in

Rhonda Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>G-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Maurice J. Rosema Jan. 4 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-3
GLO - 1838 by R. Whitcomb D.S. 12" Beech - N10° E .11 ch. 8" Walnut - S39° W .41 ch.
Clapp - 1976 per L.C.R.C. rec. in L. 3, P. 86 (over)
Englert - 1976 per L.C.R.C. rec. in L. 3, P. 101 (over)
Campbell - 1980 per L.C.R.C. rec. in L. 4, P. 74 (over)
Joiner - 1988 per L.C.R.C. rec. in L. 5, P. 327 (over)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3
Found C.I. mon. 0.5' below grade
found P.K. nail in SW. side (cut off) Power pole - N45° W 45.52'
Found nail and tag in E. side Power pole - N22° W 48.84'
Found nail and tag in E. side wood sign post - N10° W 53.33'

I hereby accept this corner as a correct and accurate perpetuation position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3
C.I. mon.
Set nail and remon. tag in SE. side 15" Maple - S73° W 92.50'
Set nail and remon. tag in SW. side (cut off) Power pole - N45° W 45.52'
Set nail and remon. tag in E. side Power pole - N22° W 48.84'
Set nail and remon. tag in E. side wood sign post - N10° W 53.33'



P.A. 345 OTTAWA COUNTY

PEER APPROVED 4/18/94

[Signature]
Date April 18, 1994

Signed by Maurice J. Rosema
Surveyor's Michigan License No. 27459

Part A - continued

Clapp - 1976 per L.C.R.C. rec. in L. 3, P. 86

Iron

Power pole - N15° W 48.5'

Tele. pole - S40° E 45.5'

Englert - 1976 per L.C.R.C. rec. in L. 3, P. 101

1" Pipe

Power pole - SE. 45.32'

Power pole - NNW. 48.50'

Tele. pole - NW. 45.55'

Campbell - 1980 per L.C.R.C. rec. in L. 4, P. 74

1" Pipe

Power pole - SE. 45.32'

Power pole - NNW. 48.50'

Tele. pole - NW. 45.55'

Joiner - 1988 per L.C.R.C. rec. in L. 5, P. 327

Iron bar

Power pole - NNW. 48.33'

Cut off Power pole - NW. 45.55'

Wood sign post - N. 53.31'

4" tree - NNE. 60.72'