

SURVEY & REMONUMENTATION

APR 24 1935

Ottawa County Remonumentation

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 15 AM 11:53

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

D. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Maurice J. Rosema Oct. 19 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-6
GLO - 1838 by VanKooten - 1972 per L.C.R.C. Rosema - 1985 per L.C.R.C.
R. Whitcomb D.S. rec. in L. 1, P. 765 (over) (over)
10" Beech - N26°W .6 ch.
12" Walnut - S1 1/2°W .22 ch. Englert - 1972 per L.C.R.C.
rec. in L. 1, P. 707 (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-6
Found C.I. mon. (0.6' below grade)
Found nail in E. side 24" Maple - N9°W 137.98'
Found nail in SE. side Power pole - S50°W 79.55'
Found nail in SE. side Power pole - S57°E 102.73'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
M. D. Nedewell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-6
C.I. mon.
Set nail and remon. tag in E. side 24" Maple - N9°W 137.98'
Set nail and remon. tag in NW. side 13" Ash - S46°W 34.77'
Set nail and remon. tag in SE. side Power pole - S50°W 79.55'
Set nail and remon. tag in NE. side Power pole - S57°E 102.73'



Dec. 10, 1994

Signed by *M. J. Rosema* Date _____
Surveyor's Michigan License No. 27459

Part A - continued

Englert - 1972 per L.C.R.C. rec. in L. 1, P. 765

T-iron

Nail in side Power pole - Sw. 79.50'

Nail in side T. pole - SSE. 98.73'

Nail in side Power pole - SE. 102.66'

Sq. spike in side 20" Maple - NNW. 137.97'

Englert - 1972 per L.C.R.C. rec. in L. 1, P. 707

1" pipe

Power pole - SE. 102.68'

T. pole - SSE. 98.3'

Street sign - NW. 41.05'

Centerline of 6" Balsam - W. 25.55'

Rosema - 1985 per L.C.R.C.

C.I. mon.

P.K. nail in SE. side Power pole - SW. 79.50'

P.K. nail in NE. side Power pole - SE. 102.66'

Nail in E. side 24" Maple - NNW. 137.91'

On centerline of gravel roads N., S., E.

0000
0000
0000
0000
0000
0000
0000
0000
0000
0000