

SURVEY & REMONUMENTATION

APR 24 1995

Ottawa County Remonumentation

RECORDED

94 DEC 15 AM 11:53

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Daphne Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

COMMISSION
For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Maurice J.
Rosema

Oct. 19 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G-7
- | | | |
|------------------------------|-------------------------------|----------------------------|
| GLO - 1838 by | Nederveld - 1975 per L.C.R.C. | Rosema - 1985 per L.C.R.C. |
| R. Whitcomb D.S. | rec. in L. 3, P. 14 (over) | (over) |
| Set post | | |
| 12" Beech - N7 1/2°W .28 ch. | Jonker - 1978 per L.C.R.C. | Joiner - 1990 per L.C.R.C. |
| 6" Walnut - S17°W .25 ch. | rec. in L. 3, P. 331 (over) | (over) |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-7
- Found C.I. mon. (top is at road grade)
 - Found nail in SE. side Power pole - S56°W 100.80'
 - Found nail in W. side 36" Maple - S6°E 195.25'
 - Found nail in S. side 11" Locust - S87°E 34.44'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Murray P. Nederveld

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-7
- C.I. mon.
 - Set nail and remon. tag in SE. side Power pole - S56°W 100.80'
 - Set nail and remon. tag in W. side 36" Maple - S6°E 195.25'
 - Set nail and remon. tag in S. side 11" Locust - S87°E 34.44'
 - Set nail and remon. tag in SW. side 9" Locust - N42°W 74.92'
 - On centerline of roads N., S., W.



Dec. 10, 1994

Signed by *Maurice J. Rosema*
Surveyor's Michigan License No. 27459

Date _____

Part A - continued

Nederveld - 1975 per L.C.R.C. rec. in L. 3, P. 14

Bt. spike

Street sign - ESE. 16.3'

Nail in Power pole - Sw. 102.00'

Nail in 36" Maple - SSE. 194.75'

Jonker - 1978 per L.C.R.C. rec. in L. 3, P. 331

5/8" round iron

Nail in face of Power pole - SW. 100.57'

c/l street sign post - ESE. 18.0'

Spike in W. side 36" Maple - SSE. 195.2'

Nail on N. side Lucust clump - E. 27.38'

Rosema - 1985 per L.C.R.C.

5/8" round iron

c/l street sign - E. 26.20'

Nail in W. side 36" Maple - ESE. 195.39'

Nail in face of Power pole - SW. 100.43'

On centerline of gravels roads N.-S.-W.

Joiner - 1990 per L.C.R.C.

C.I. mon.

Nail in W. side 36" Maple - SSE. 195.39'

Nail in face of Power pole - SW. 100.43'

c/l steel pipe street sign - E. 26.20'

At c/l gravels roads N.-S.-W.

1990
150
100
50
00