

**SURVEY &  
REMONUMENTATION**

Ottawa County Remonumentation  
**APR 05 1996** LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970  
**COMMISSION**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R13W</u>	G-8
	T _____ R _____	(E $\frac{1}{2}$ cor. of
	T _____ R _____	Sec. 21)
	T _____ R _____	Tallmadge Twp
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RECORDED**

95 NOV 29 PM 1:45

*Elizabeth Holbrook*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Maurice J. Rosema in a field survey on Sept. 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-8  
 GLO - 1838 (R. Whitcomb D.S.) L.C.R.C. recorded in Liber 2,  
 20" Beech N58°E 16lks Page 613 - September 27, 1974  
 20" Beech S20°W 33lks (over)

L.C.R.C. recorded in Liber 6,  
 Page 177 - October 10, 1991  
 (over)

PA. 345 OTTAWA COUNTY  
 PEER APPROVED 11-20-95

*Richard P. Redwood*  
*YDN*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8  
 Found C.I. monument in monument box  
 Found PK nail in top of wood fc post SE 54.43'  
 Found nail in NE side 13" Hickory WNW 27.39'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8  
 C.I. monument in monument box in gravel road  
 Set nail and Ottawa County remon. tag in top of wood fc post S52°E 54.43'  
 Set nail and Ottawa County remon. tag in NE side Hickory N57°W 27.39'  
 Set nail and Ottawa County remon. tag in W side 9" Elm N25°E 73.58'  
 Set nail and Ottawa County remon. tag in E side 8" Basswood N24°W 44.12'  
 Set nail and Ottawa County remon. tag in W side 7" Elm S17°W 78.38'  
 c/l N-S gravel road E 4'  
 fc to E S 31'

Signed by *Maurice J. Rosema* Date October 21, 1995  
 Surveyor's Michigan License No. 27459

G-8, T7N, R13W

L.C.R.C. recorded in Liber 2, Page 613

- July 3, 1974

5/8" copperweld rod in monument box

25" W Cherry	S85°W 59.09'
MBT pole	N80°E 33.56'
T-iron	E 33.00'
9" Cherry	N45°W 67.00'

L.C.R.C. recorded in Liber 6, Page 177

- October 10, 1991

C.I. monument

Shagbark Hickory	NW 27.39'
8" Basswood	NNW 44.61'
PK on fc post	SE 54.04'
18" Elm	NE 47.45'

\$ 11.00 CORNER