

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County Remonumentation

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

DEC 15 AM 11:48

Daphne Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa

(County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>G-12</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Maurice J.
Rosema

I, _____, in a field survey on Oct. 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-12
GLO - 1838 by Joiner - 1981 per L.C.R.C. rec. in L. 4, P. 262
R. Whitcomb D.S. C.I. mon.
10" Elm - N. .13 ch. 14" Oak - SSE. 11.6'
10" Lym. - S56°E .15 ch. 4" Maple - ESE. 23.9'
7" Maple - S. 15.9'
E. edge S. side of conc bridge footing - W. 4.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


G-12
Found C.I. mon. 0.3 below grade
Found nail in W. side 9" Maple - S43°W 16.00'
Found nail in W. side 16" Oak - S13°W 11.65'
Found nail in N. side 6" Maple - S30°E 23.92'
E. edge of S. side of conc. bridge footing - N50°W 21.45'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Harold D. Hodowald

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12
C.I. mon.
Set nail and remon. tag in W. side 9" Maple - S43°W 16.00'
Set nail and remon. tag in W. side 16" Oak - S13°W 11.65'
Set nail and remon. tag in N. side 6" Maple - S30°E 23.92'
Set nail and remon. tag in N. side 5" Maple - N50°W 21.45'



Signed by *Maurice J. Rosema* Date Dec. 10, 1994
Surveyor's Michigan License No. 27459