

**SURVEY & REMONUMENTATION**

DEC 01 1998

**SECTION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ottawa <small>(County)</small>	Located In: Georgetown Township	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	G-13
	T _____ R _____	SW Cor.
	T _____ R _____	Sec. 34
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**RECORDED**

98 JUL 24 PM 1:47

*[Signature]*

REGISTER OF DEEDS  
OTTAWA COUNTY, MI

**Register of Deeds Stamp & File Number**

I, Rodney D. Unema, in a field survey on June 24, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G-13  
G.L.O. 1830, Lucius Lyon  
Set post at 80.00 chains  
12" W. Oak N86°E 29 links  
7" B. Ash N65°W 25 links

No recorded L.C.R.C. Witnesses or other corner information furnished

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-13  
No evidence of corner found. Held Gov't. jog of 15.84 feet (24 links)  
East of corner, G-1 T6N, R13W (*FOUND "T" IRON WHICH MATCHES PREVIOUSLY RECORDED POSITION*)

\*See reverse side for sketch

Set Ottawa Co. Cap on 3/4" X 36" Steel Bar  
And is accepted as a careful and faithful reestablishment of the position of the original corner.

OTTAWA COUNTY  
REGISTERED 7-20-98

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-13 - SW Corner, Section 34  
Ottawa Co. Cap on 3/4" X 36" Steel Bar

Set nail & O.C. tag in NE side 18" Maple	N70°W	11.82'
Set nail & O.C. tag in S side 12" Ash	S80°E	27.95'
Set nail & O.C. tag in SE side 8" Ash	S31°W	25.70'
Set nail & O.C. tag in E side 14" Ash	N20°E	36.90'
G-1, T6N, R13W,	West	15.84'



Signed by Rodney D. Unema Date June 30, 1998  
Surveyor's Michigan License No. 33987

SURVEY &  
REMONUMENTATION

DEC 01 1998

SECTION

N52327

SEC. 33-7-13

SEC. 34-7

