

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:53

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Polycia Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Maurice J.
Rosema

Nov. 26 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-7
GLO - 1838 by Nederveld - 1974 per L.C.R.C. Joiner - 1991 per L.C.R.C.
R. Whitcomb rec. in L. 2, P. 665 (over) rec. in L. 6, P. 187 (over)
Set post
Rosema - 1985 per L.C.R.C.
rec. in L. 5, P. 232 (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7
Found C.I. mon. (top broken)
Found nail in SE. side 12" Maple - N62°E 29.29'
Found nail in N. side 8" Oak - N90°E 23.70'
Found nail in NE. side 24" Maple - S43°E 38.53'
Found nail in E. side 6" Oak - S19°W 23.13'
On NE. edge 12" Elm, on W. edge of woods N.-S., on S. edge of lane to E.

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Harold P. Nederveld

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7
C.I. mon (top broken)
Set nail and remon. tag in SE. side 12" Maple - N62°E 29.29'
Set nail and remon. tag in N. side 8" Oak - N90°E 23.70'
Set nail and remon. tag in NE. side 24" Maple - S43°E 38.53'
Set nail and remon. tag in E. side 6" Oak - S19°W 23.13'
Set nail and remon. tag in N. side 24" Maple - S65°E 44.27'
One NE. edge 12" Elm, on W. edge of wood N.-S., on S. edge of lane to E.



Dec. 10, 1994

Signed by *Maurice J. Rosema* Date _____
Surveyor's Michigan License No. 27459

Part A - continued

Nederveld - 1974 per L.C.R.C. rec. in L. 2, P. 665

2" iron

Nail in 6" Ash - NNE. 12.89'

Nail in 8" Ash - NE. 29.30'

Nail in 26" Maple - ENE. 83.60'

Nail in 18" Maple - SE. 38.50'

Fence lines N., S. and E.

Rosema - 1985 per L.C.R.C. rec. in L. 5, P. 232

2" iron on E. edge of 8" Elm

Nail in SE. side 10" Oak - NE. 29.35'

Nail in NE. side 24" Maple - SE. 38.53'

Nail in N. side 6" Oak - E. 23.80'

Nail in NE. side 24" Maple - ESE. 44.25'

On W. edge of woods

On fence line N.-S.-E.

On S. edge of lane to E.

Joiner - 1991 per L.C.R.C. rec. in L. 6, P. 187

C.I. mon.

10" Oak - E. 23.72'

12" Oak - NE. 29.33'

24" Maple - SE. 44.30'

8" Oak - NNE. 23.12'

1220 #
9-100
CORNER
CORNER
CORNER
CORNER

1220 #
9-100
CORNER
CORNER