

**SURVEY &
REMONUMENTATION**

APR 05 1996

Ottawa County Remonumentation

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R13W</u>	H-11.
	T _____ R _____	(S $\frac{1}{4}$ cor of
	T _____ R _____	Sec. 27)
	T _____ R _____	Tallmadge Twp
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

95 NOV 29 PM 1:45

Phyllis Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Maurice J. Rosema, in a field survey on September 27, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-11

GLO - 1838 (R. Whitcomb D.S.)
22" Hickory N22°E 22lks
10" Lym S22°W 7 lks

L.C.R.C. recorded in Liber 3,
Page 166 - May 5, 1977
(over)

L.C.R.C. recorded in Liber 5,
Page 331 - August 4, 1988
(over)

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11-20-95

Murray D. Newbold
M.D.N.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11

Found capped rerod in Mon Box and replaced with 3/4" X 2" steel rod with Ottawa County remon. cap

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11

3/4" X 2" steel rod with Ottawa County remon. cap in Mon box
Set nail and Ottawa County remon. tag in E side 12" Hickory
c/l street sign (at base)
Set nail and Ottawa County remon. tag in S side 7" Cherry
(4' high)
c/l street sign
Set nail and Ottawa County remon. tag in top of wood post
Set nail and Ottawa County remon. tag in top of wood post
On c/l gravel road to S
c/l bit. conc. road (on curve)

N2°W 63.12'
S53°W 23.45'
N85°W 46.13'
N84°W 26.32'
S20°W 98.05'
S45°E 31.15'
SE 13'

Signed by Maurice J. Rosema

Date October 21, 1995

Surveyor's Michigan License No. 27459

H-11, T7N, R13W

L.C.R.C. recorded in Liber 3, Page 166

- May 5, 1977

3/4" iron

Nail in side 10" Elm SSW 25.94'

Nail in side 8" Apple WSW 20.99'

Nail in side 16" Hickory NE 60.94'

c/l 20th Avenue E 15.0'

L.C.R.C. recorded in Liber 5, Page 331

- August 4, 1988

C.I. monument

18" Hickory ESE 60.84'

8" Hickory NNW 34.62'

8" Hickory NNW 34.62'

8"-10"-12" tri Apple WSW 20.90'

\$ 11.00 CORNER