

DEC 01 1998

SECTION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa

	Located In:	Corner Code #
	Georgetown Township	
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>H-13</u>
	T _____ R _____	<u>S 1/4 Cor.</u>
	T _____ R _____	<u>Sec. 34</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
98 JUL 24 PM 1:47

Long Schultz
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Rodney D. Unema, in a field survey on June 24, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13
G.L.O. 1830, Lucius Lyon
Set H.W.P. @ 40 chains
20" Hackberry N44°E 58 links
24" Hackberry N26°W 40 links

No recorded L.C.R.C. Witnesses:
From County Records (no date)
Found stake (iron on top)
16" Elm SE 29.2'
26" Elm NW 46.2'
30" Oak SW 28.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13
No evidence of corner, witnesses, or occupation lines were found during field survey. Corner was placed on Township line midway and on line between SW corner, Section 34 (G-13) and SE corner (I-13), and is accepted as a careful and faithful reestablishment of the position of the original corner.
Set Ottawa Co. Cap on 3/4" X 36" steel bar

*See reverse side for sketch

P.A. 845 OTTAWA COUNTY

FILED APPROVED 7-20-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 S 1/4 Corner, Section 34
Ottawa Co. Cap on 3/4" X 36" Steel Bar - on trail running E-W
Set nail & O.C. tag in S'ly side 14" Elm N65°W 64.63'
Set nail & O.C. tag in NE side 16" Maple N42°W 59.47'
Set nail & O.C. tag in W side 16" Elm N03°E 45.54'
Set nail & O.C. tag in NW side 12" Ash N39°E 47.22'
Set nail & O.C. tag in NW side 20" Elm S59°W 35.06'
H-1, T6N, R13W West 4.49'
S'ly Edge of Grand River North 120'+



Signed by Rodney D. Unema
Surveyor's Michigan License No. 33987

Date June 30, 1998

SURVEY &
REMONUMENTATION

DEC 01 1998

SECTION

- 7 - 13

SEC. 34 - 7 - 13

