

SURVEY & REMONUMENTATION

FEB 27 1998

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION
Ottawa
(County)

Located In: _____ Corner Code ##

1. Public Land Survey		T <u>7N</u> R <u>13W</u>		I-2	
		T _____ R _____		_____	
		T _____ R _____		_____	
		T _____ R _____		_____	
2. Property Controlling in Section	S _____	T _____ R _____		_____	
	S _____	T _____ R _____		_____	
3. Miscellaneous Property in Sec.	S _____	T _____ R _____		_____	
	S _____	T _____ R _____		_____	

RECORDED
97 DEC -8 AM 11:28

Dan Schultz
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Maurice J. Rosema, in a field survey on Dec. 31, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
I-2

G.L.O. by R. Whitcomb in 1838 Set post 16" Maple N67½°E 10 lks 15" Sugar S58°W 9 lks	L.C.R.C. rec. in Liber 5, Page 185 on Dec. 27, 1984 C.I. monument Fence corner P. pole NW cor. garage P. pole	W 51.30' E 35.68' NE 76.40' NNE 70.90'
--	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I-2

Found C.I. monument in monument box
Found nail in S side of P. pole S83°E 35.75'
Found nail in W side P. pole N30°E 70.90'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 9-16-96

YDZ

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-2

C.I. monument Set nail and remon tag in S side P. pole	S83°E 35.75'
Set nail and remon tag in S side wood fence post	N79°W 52.90'
Set nail and remon tag in N side wood fence post	N89°W 58.75'
Set nail and remon tag in W side P. pole	N30°E 70.90'
Set nail and remon tag in N side mailbox post	S33°E 47.72'



\$9.00 CORNER
\$1.00 PHOTO

Signed by *Maurice J. Rosema* Date Sept. 16, 1996
Surveyor's Michigan License No. 27459