

Ottawa County remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 15 AM 9:28

D. J. Holman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 7N R 13W I-3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Maurice J. Rosema in a field survey on Aug. 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-3 Nederveld - 1974 per L.C.R.C. recorded in Liber 2, Page 669
1" iron
Spike in tw. 16" Ash - NNW. 101.00'
- Campbell - 1980 per L.C.R.C. recorded in Liber 4, Page 73
1" iron
P. pole - N45°E 46.51'
Guy pole - S45°E 40.85'
26" Ash - S60°W 67.62'
Tw. 16" Ash - N20°W 101.00'
- Joiner - 1984 per L.C.R.C. recorded in Liber 5, Page 184
C.I. monument
P. pole - NE. 46.56'
Guy pole - SE. 41.00'
Street sign - S. 28.75'
26" Ash - WSW. 67.59'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-3 Found C.I. monument (0.4' below surface)
- Found P.K. nail in SE. side guy pole - S60°E 41.00'
- Found P.K. nail in SE. side P. pole - N45°E 46.56'
- Spike in N. side 35" Ash - S65°W 67.57'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original section corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-3 C.I. monument
- Set nail and O.C. remon. tag in NW. side 18" Ash - S22°W 42.49'
- Set nail and O.C. remon. tag in N. side guy pole - S60°E 41.00'
- Set nail and O.C. remon. tag in SE. side P. pole - N45°E 46.56'
- Set nail and O.C. remon. tag in N. side 35" Ash - S65°W 67.57'
- On centerline of E-W gravel road and on centerline of gravel road to N



Signed by

Maurice J. Rosema
Maurice J. Rosema - Tru-Line Surveying
Surveyor's Michigan License No. 27459

Date October 02, 1993