

**SURVEY &  
DOCUMENTATION**

Ottawa County Remonumentation  
**APR 05 1996 LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**COMMISSION**

Ottawa <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	I-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RECORDED**  
 95 NOV 29 PM 1:37  
*Rhonda L. Callahan*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Maurice J. Rosema in a field survey on Sept. 1, 1995  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**


A. Description of original monument and accessories and/or subsequent restoration:  
 I-8  
 Original gov't cor. set in 1838 by R. Whitcomb  
 L.C.R.C. per Liber 6, Page 187 recorded Nov. 6, 1991  
 Cast Iron monument  
 Set post 18" Maple W 19.71'  
 8" Tamerack S42°W 9 lks. 14" Maple SSE 19.47'  
 8" Tamerack N81°E 13 lks. 30" Maple E 43.85'  
 36" Maple SSW 28.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 I-8  
 Found Cast Iron monument  
 Found nail in S side 18" Maple S86°W 19.70'  
 Found nail in SW side 15" Maple S38°E 19.45'

**P.A. 345 OTTAWA COUNTY**  
**PEER APPROVED** 11/20/95  
*Richard D. McDowell*  
 RDT

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 I-8  
 Cast Iron monument  
 Set nail and O.C. tag in W side 5" Elm S48°W 17.20'  
 Set nail and O.C. tag in S side 18" Maple S86°W 19.70'  
 Set nail and O.C. tag in SW side 15" Maple S38°E 19.45'  
 Set nail and O.C. tag in W side 4" Maple N10°E 18.50'  
 Center of base of steel fence post (at W end of fence line to E) E 0.60'  
 Base of T fence post N1°E 15.26'



Signed by *Maurice J. Rosema* Date Nov. 14, 1995  
 Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 19  
 REVISED MAY 14, 19  
 REVISED JAN., 19