

SURVEY & MONUMENTATION

APR 05 1996

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Ottawa (County) Located In: Corner Code #1

1. Public Land Survey	T	<u>T7N</u>	R	<u>R13W</u>	I-10
	T	_____	R	_____	(E 1/4 cor. of
	T	_____	R	_____	Sec. 27)
	T	_____	R	_____	Tallmadge Twp
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

RECORDED

95 NOV 29 PM 1:45

Edythe S. Daulton
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Maurice J. Rosema, in a field survey on Sept. 27, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10
 GLO - 1838 (R. Whitcomb D.S.) L.C.R.C. recorded in Liber 1,
 10" Pine N57°E 5lks Page 573 - July 26, 1972
 20" White Oak S15°W 5lks (over)

L.C.R.C. recorded in Liber 6,
 Page 178 - October 10, 1991
 (over)

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 11-20-95

Keddy P. Nedewell
JDR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10
 Found C.I. monument
 Found nail in E side 26" Pine clump S35°E 14.91'
 Found nail in NW side 13" Oak S41°W 43.64'
 Found nail in S side 14" Pine S60°W 20.05'
 Found nail in W side 14" Oak N54°E 39.75'



I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10
 Found C.I. monument
 Set nail and Ottawa County remon. tag in E side 26" Pine clump S35°E 14.91'
 Set nail and Ottawa County remon. tag in S side 13" Oak S89°W 46.63'
 Set nail and Ottawa County remon. tag in NW side 13" Oak S41°W 43.64'
 Set nail and Ottawa County remon. tag in S side 14" Pine S60°W 20.05'
 Set nail and Ottawa County remon. tag in W side 14" Oak N54°E 39.75'

Signed by *M. J. Rosema* Date October 21, 1995
 Surveyor's Michigan License No. 27459

I-10, T7N, R13W

L.C.R.C. recorded in Liber 1, Page 573
- July 26, 1972

C.I. monument
24" quad Pine SSE 15.00'
10" Oak SW 43.72'
8" Pine NW 20.12'

L.C.R.C. recorded in Liber 6, Page 178
- October 10, 1991

C.I. monument
26" quad Pine SSE 14.95'
11" Oak SW 43.61'
14" Pine NW 20.12'
13" Oak NE 39.78'

\$ 11.00 CORNER