

**SURVEY & REMONUMENTATION**

DEC 01 1998

**SECTION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> (County)	Located In: Georgetown Township	Corner Code #/
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>I-13</u> SW Cor. Sec. 35
	T ___ R ___	___
	T ___ R ___	___
	T <u>6N</u> R <u>13W</u>	<u>I-1</u>
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

**RECORDED**  
98 JUL 24 PM 1:47

*Rodney D. Unema*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Rodney D. Unema, in a field survey on May 21, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-13 G.L.O. 1837 L: Lyon-set post 6" Hickory N48°E 16 Links 7" Hickory N58°W 20 Links	No recorded L.C.R.C.'s for L-13	From County Witness Map Iron 6" Oak NE 31.0' 6" Oak SW 39.0' Common corner
---	---------------------------------	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13  
Found 3/4" Iron Pipe on Peninsula of land  
No remaining witnesses were found due to earth work and landscaping etc. around corner. Location of corner checks within 0.2' of position measured in 1977 and 1979 in Sec. 2-6-13 and Sec. 35-7-13 by Exxel Engineering.  
Accepted as a careful and faithful perpetuation of the position of the original corner, and replaced 3/4" Iron with standard Ottawa County cap on 3/4" X 36" steel bar.

\*Over for sketch

OTTAWA COUNTY  
REGISTERED 6-1-98  
*R.D.U.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Ottawa County Cap on 3/4" X 36" Steel Bar	N10°W 39.26'
Set Nail & O.C. tag in E side 14" Ash	N40°W 19.46'
Set Nail & O.C. tag in NE side 12" Ash	N90°W 35.12'
Set Nail & O.C. tag in S side 12" Oak	S0°E 19.45'
Set Nail & O.C. tag in W side 6" Cottonwood	East 5'
Water's edge	S55°W 34'
Water's edge	

Corner is common with I-1, T6N, R13W



Signed by *Rodney D. Unema* Date May 29, 1998

Surveyor's Michigan License No. 33987

SURVEY & REMONUMENTATION

DEC 01 1998

SECTION

