

1883

RECORDED

93 DEC 15 AM 9:27

COMMISSION

Ottawa County remonumentation
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

D. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 7N R 13W J-5
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Maurice J. Rosema, in a field survey on Aug. 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

- J-5 Joiner - 1981 per L.C.R.C. recorded in Liber 4, Page 259
C.I.M.
P. pole - NE. 78.11'
T. pole - NW. 58.66'
St. sign - S. 23.45'
Fence post - SW. 42.27'
- Rosema - 1988 per L.C.R.C. recorded in Liber 5, Page 315
C.I.M.
P.K. nail in S. side P. pole - ENE. 78.10'
P.K. nail in E. side T. pole - NNW. 57.69'
c/l st. sign - S 23.40'
P.K. nail in NW. side RR. tie fc. post - SW. 42.43'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-5 Found C.I. monument (0.3' below grade)
Found P.K. nail in E. side T. pole - N20°W 57.65'
Found P.K. nail in S. side P. pole - N74°E 78.06'
c/l base of street sign - S2°E 23.30'
Found P.K. nail in NW. cor. RR. tie fence post - S44°W 42.55'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original section corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-5 C.I. monument
Set nail and O.C. remon. tag in N. side 18" Elm - S80°W 107.04'
Set nail and O.C. remon. tag in E. side T. pole - N20°W 57.65'
Set nail and O.C. remon. tag in S. side P. pole - N74°E 78.06'
Set nail and O.C. remon. tag in NW side RR. tie fence post - S44°W 42.55'
on centerline of E-W gravel road, centerline of gravel road to N. - E. 4'

Signed by Maurice J. Rosema
Surveyor's Michigan License No. 27459

Date October 02, 1993