

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 18 PM 4: 56

R. J. Rosema
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in
Ottawa
 (County)

Located In: Corner Code #

	7N	13W	J-11
1. Public Land Survey	T	R	(S $\frac{1}{2}$ cor. Sec. 26)
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Maurice J. Rosema Nov. 29, 1996

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-11	Information from rec. survey map rec. in L. 2, P. 210	Information from the files of Nederveld Associates
GLO 1838 by Whitcomb Post	iron	T-iron
12" Pine - N87°E 19 lks	10" Oak - NE 11.42'	Nail and cap in S side 8" Oak - W 4.51'
14" W Oak - N6°E 15 lks	18" Oak - E 28.40'	Nail and cap in NW side 8" Oak - S15°E 10.89'
Information from the files of Tru-Line Surveying P.C. (over)	10" Oak - SE 29.55'	Nail and cap in SW side 18" Oak - S45°E 30.06'
	12" Oak - SW 32.65'	
	10" Oak - NW 29.65'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Nail and cap in E. side 18" Oak - N35°W 26.78'

J-11
 Found T-iron, replaced of 5/8" x 3' steel rod with remon. cap
 Found spk and tag in S side 8" Oak - W 4.52'
 Found spk and tag in NW side 8" Oak - SW 10.90'
 Found spk and tag in SW side 18" Oak - SE 30.05'
 Found spk and tag in E side 17" Oak - N 26.72'

OT TOWN OF OTTAWA COUNTY
 PEER APPROVED 12-9-96

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

M.J.R.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11
 5/8" x 3' steel rod with remon. cap
 Nail and remon. tag in E side 17" Oak - N10°W 26.75'
 Nail and remon. tag in S side 8" Oak - S81°W 4.53'
 Nail and remon. tag in NW side 8" Oak - S22°W 10.92'
 Nail and remon. tag in E side 18" Oak - S54°E 29.90'
 Nail and remon. tag in S side 12" Oak - N35°E 36.64'
 Steel fence post - N45°W 0.35'



Signed by *Maurice J. Rosema* Date Dec. 9, 1996
 Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 19
 REVISED MAY 14, 19
 REVISED JAN., 19

Information from the files of Tru-Line Surveying P.C.
T-iron

Nail and tag no 33739 in S side 8" Oak - W 4.53'

Nail and tag no. 33739 in NW side 8" Oak - SSW 10.92'

Nail and tag no. 33739 in W side 18" Oak - SE 30.10'

Nail and tag no. 33739 in E side 18" Oak - NNW 26.74'