

**SURVEY &  
REMONUMENTATION**

Ottawa County Remonumentation

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:53

**COMMISSION**

For corners in

*Dorothy Carloman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>K-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Maurice J.  
Rosema

Dec. 9 94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-2  
GLO - 1838 by Spicer - 1974 per L.C.R.C. Rosema - 1988 per  
R. Whitcomb rec. in L. 2, P. 449 L.C.R.C. rec. in  
Post (over) L. 5, P. 316  
12" Beech - S17°E .12 ch. Joiner - 1984 per L.C.R.C. (over)  
20" Walnut - N18.5°W .26 ch. rec. in L. 5, P. 184  
(over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2  
Found C.I. mon. in mon. box  
Found P.K. nail in S. side Power pole - S78°W 33.59'  
Found P.K. nail in N. side Power pole - S89°E 50.79'  
Found Nnail in SW. side 10" Maple - S72°E 57.32'

P.A. 345 OTTAWA COUNTY

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

PEER APPROVED 12/12/94

*Madon P. Hesterwell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2  
C.I. mon. in mon. box  
Set nail and remon. tag in S. side of Power pole - S78°W 33.59'  
Set nail and remon. tag in N. side of Power pole - S89°E 50.79'  
Set nail and remon tag in SW. side of 10" Maple - S72°E 57.32'  
Set nail and remon. tag in SW. side 6" Ash - S50°W 42.17'



Signed by *Maurice J. Rosema*  
Surveyor's Michigan License No. 27459

Date Dec. 10, 1994

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1981  
REVISED MAY 14, 1983  
REVISED JAN. 1988

Part A - continued

Spicer - 1974 per L.C.R.C. rec. in L. 2, P. 449

3/4" iron

NE. cor. house - S50° W 98.3'

Centerline of CP/MBT pole - S75 W 26.9'

Centerline of CP/MBT pole - E. 52.05'

Joiner - 1984 per L.C.R.C. rec. in L. 5, P. 184

C.I. mon.

Tri. Maple - NNW. 70.90'

Power pole - E. 51.98'

Power pole - WSW. 33.58'

8" tree - ESE. 45.81'

Rosema - 1988 per L.C.R.C. rec. in L. 5, P 316

C.I. mon:

Nail in S. side 10" Maple - ESE. 57.39'

P.K. nail in S. side Power pole - WSW 33.58'

P.K. nail in N. side Power pole - E. 50.81'

2006 #  
2006 #  
2006 #  
2006 #