

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:49

Robert H. Williams
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>K-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Maurice J. Rosema, in a field survey on Jan. 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6 Clapp - 1976 per L.C.R.C. recorded in L. 3, P. 98 T-iron Conc. mon. - E. 33.00' T. pole - SSW. 99.43' Twin 8" Ash - W. 41.19'	Englert - 1977 per L.C.R.C. recorded in L. 3, P. 179 T-iron 8" Box Elder - W. 41.03' 12" Basswood - E. 69.40' 40" Maple - NE. 119.85'	Merdzinski - 1978 per L.C.R.C. recorded in L. 3, P. 263 T-iron above 1/2" rebar Nail in S. side 8" Ash - N85°W 41.09' Nail in W. side 20" Walnut - N25°E 140.04'
---	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

K-6
 Found C.I. mon. in mon. box
 Found nail in S. side 11" tw. tree - S88°W 41.01'
 Found broken conc. mon. - S88°E 32.64'
 Found nail in NW. side 32" Oak - N13°E 140.08'

I hereby accept this corner as correct and accurate perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 4/18/94
Robert D. Nedeweld

Nail in top c/l end fence post - N70°E 33.76'
 PK nail in S. side twin 10" Poplar - E. 69.42'
 On c/l of 20' wide blacktop road
 G.L.O. - 1838 signed by R. Whitcomb D.S.
 10" Beech - S67°W .29 ch.
 6" Sugar - N58°E .30 ch.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6
 C.I. mon. in mon. box
 Set nail and remon. tag in S. side 11" tw. tree - S88°W 41.01'
 Set nail and remon. tag in SE. side 14" Elm - N62°E 39.47'
 Set nail and remon. tag in NW. side 32" Oak - N13°E 140.08'
 c/l E.-W. Ponderosa Drive S. 133'±
 Broken conc. mon. - S88°E 32.64'
 On c/l N.-S. bit. conc. road



Signed by Maurice J. Rosema Date April 18, 1994
 Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983