

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County Remonumentation

RECORDED

LAND CORNER RECORDATION CERTIFICATE 94 DEC 15 AM 11:54
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Phyllis Robinson
REGISTER OF DEEDS
OT TAWA COUNTY, MI

| Ottawa (County) | Located In: | Corner Code # |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>7N</u> R <u>13W</u> | <u>K-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Maurice J.
Rosema

Dec. 9 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|----|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | | 17 | | 18 | | 19 | | 20 | | 21 | | 22 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

K-10
GLO - 1838 by Englert - 1976 per L.C.R.C. Glaza - 1989 per L.C.R.C.
R. Whitcomb rec. in L. 3, P. 138 (over) rec. in L. 6, P. 1 (over)
Set post
6" Pine - N75 W .69 ch. Joiner - 1981 per L.C.R.C.
rec. in L. 4, P. 291 (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10
Found 1" solid iron stake in mon. box, replaced with 3/4" x 2' steel rod with standard remon. cap
Found nail in NE. side 13" Maple clump - N63°W 44.05'
Found nail in E. side fence post - S62°W 43.90'
Found nail in W. side Power pole - S84°E 54.88'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10
3/4" x 2' steel rod with standard remon. cap in mon. box
Set nail and remon. tag in NE. side 13" Maple clump - N63°W 44.05'
Set nail and remon. tag in N. side fence post - S62°W 43.90'
Set nail and remon. tag in N. side Power pole - S84°E 55.32'
Set nail and remon. tag in NE. side 8" Ash - S55°E 44.69'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Murray P. Hedrick



Signed by *Maurice J. Rosema* Date Dec. 10, 1994
Surveyor's Michigan License No. 27459

Part A - continued

Englert - 1976 per L.C.R.C. rec. in L. 3, P. 138

T-iron

Power pole - E. 55.14'

Tw. Maple - NW. 78.00'

12" Maple - W. 55.41'

Joiner - 1981 per L.C.R.C. rec. in L. 4, P. 291

C.I. mon.

Fence post - SW. 43.63'

Tw. 12" Maple - WNW. 43.17'

Power pole - E. 54.68'

Glaza - 1989 per L.C.R.C. rec. in L. 6, P. 1

MVK rerod

Nail in N. side 12" Maple clump - N60°W 44.10'

Nail in N. side Power pole - E. 55.32'

Nail in NE. side fence post - S60°W 43.59'

1989
1000
1000
1000
1000