

**SURVEY &  
MONUMENTATION**

Ottawa County Remonumentation  
**APR 05 1996** LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**COMMISSION**

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	L-5
	T _____ R _____	(S $\frac{1}{4}$ cor of
	T _____ R _____	Section 12)
	T _____ R _____	Tallmadge Twp
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RECORDED**

**95 NOV 15 PM 2:06**

*D. J. ...*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Maurice J. Rosema, in a field survey on February 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 L-5

GLO - 1838 (R. Whitcomb D.S.)  
 24" Oak S55°E 36lks  
 15" Sugar N20°W 24lks

L.C.R.C. recorded in Liber 1,  
 Page 609 - August 14, 1972  
 (over)

**P.A. 345 OTTAWA COUNTY**

L.C.R.C. recorded in Liber 6,  
 Page 178 - October 10 1991  
 (over)

PEER APPROVED 10/23/95

*M. J. Rosema*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 L-5

Found C.I. monument in Mon box  
 Found nail in 33" Spruce NE 47.95'  
 Found nail in F. Post S 34.53'  
 Found nail in 20" Maple SW 51.08'  
 Found nail in P. pole NW 96.47'



I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5  
 Found C.I. monument in monument box  
 Set nail and Ottawa County remon. tag in W side 33" Spruce N24°E 47.95'  
 Set nail and Ottawa County remon. tag in W side 12" tw Elm N30°W 34.53'  
 Set nail and Ottawa County remon. tag in W side fc post S4°W 35.82'  
 Set nail and Ottawa County remon. tag in NW side 21" Maple S60°W 51.08'  
 Set nail and Ottawa County remon. tag in SW side P pole N57°W 96.47'  
 On c/l E-W bit. conc. road  
 On tree row to N

Signed by *M. J. Rosema* Date October 21, 1995  
 Surveyor's Michigan License No. 27459

L-5, T7N, R13W

L.C.R.C. recorded in Liber 1, Page 609

- August 14, 1972

1" iron

Nail in side 12" Maple

SW 50.69'

Nail in T pole

NW 28.26'

Nail in side 12" Pine

NW 70.70'

L.C.R.C. recorded in Liber 6, Page 178

C.I. monument in monument box

PK nail in 30" Spruce

NE 47.89'

Nail in 20" Maple

SW 51.06'

Guy pole

NW 96.39'

Nail in fc post

S 35.75'

13-00 CORNER