

**SURVEY &  
MONUMENTATION**

Ottawa County Remonumentation

APR 05 1996

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**  
Ottawa  
(County)

Located In:

Corner Code #:

- |                                       |   |           |   |            |                                       |
|---------------------------------------|---|-----------|---|------------|---------------------------------------|
| 1. Public Land Survey                 | T | <u>7N</u> | R | <u>13W</u> | L-7                                   |
|                                       | T |           | R |            | (S <sup>1</sup> / <sub>4</sub> cor of |
|                                       | T |           | R |            | Section 13)                           |
|                                       | T |           | R |            | Tallmadge Twp                         |
| 2. Property Controlling<br>in Section | S |           | T | R          |                                       |
|                                       | S |           | T | R          |                                       |
| 3. Miscellaneous<br>Property in Sec.  | S |           | T | R          |                                       |
|                                       | S |           | T | R          |                                       |

RECORDED

95 NOV 15 PM 2:06

*Robert R. Carlsson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Maurice J. Rosema in a field survey on Feb. 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- L-7  
GLO - 1838 (R. Whitcomb D.S.) L.C.R.C. recorded in Liber 2, Page 818  
24" Sugar S59°W 18 lks - October 20, 1975 (over)  
15" Sugar S67°E 19 lks  
L.C.R.C. recorded in Liber 4, Page 47  
L.C.R.C. recorded in Liber 2, Page 471 - April 9, 1980 (over  
- May 14, 1974 (over)  
L.C.R.C. recorded in Liber 5, Page 175  
- December 27, 1984 (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-7  
Found 1/2" steel rod in monument box, replaced with 3/4" X 2" steel rod with Ottawa County remon. cap  
Found nail in E side 30" Maple NNE 22.62'  
Found nail in W side P pole NNE 38.30'  
Found PK nail in E side P pole SSW 57.68'  
Found nail in W side 42" Oak SW 32.06'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7  
3/4" X 2" steel rod with Ottawa County remon. cap in monument box  
Set nail and Ottawa County remon. tag in E side 30" Maple N20°E 22.62'  
Set nail and Ottawa County remon. tag in W side P pole N33°E 38.30'  
Set nail and Ottawa County remon. tag in NW side 25" Maple N66°W 51.01'  
Set nail and Ottawa County remon. tag in W side 42" Oak S22°W 32.06'  
Set nail and Ottawa County remon. tag in E side P pole S3°W 57.68'  
On c/l E-W bit. conc. road

P.A. 345 OTTAWA COUNTY

PEER APPROVED 10/23/95

*Murray D. Newbold*  
Date October 21, 1995

Signed by Maurice J. Rosema  
Surveyor's Michigan License No. 27459

L-7, T7N, R13W

L.C.R.C. recorded in Liber 2, Page 471

- May 14, 1974

1/2" iron	
Nail in 18" Maple	NW 51.84'
Nail in P pole	S 57.43'
Nail in P pole	ESE 117.95'
Nail in T pole	NNE 38.28'

L.C.R.C. recorded in Liber 2, Page 818

- October 20, 1975

1" iron	
18" Maple	NW 51.84'
P pole	S 57.43'
P pole	ESE 117.95'
T pole	NNE 38.28'

L.C.R.C. recorded in Liber 4, Page 47

- April 9, 1980

3/4" iron	
Nail and tag in c/l P/T pole	S5°E 57.52'
Nail and tag in c/l P/T pole	N55°W 51.80'
Nail and tag in c/l P/T pole	N30°E 38.35'
Nail in c/l 36" Maple	S30°W 31.65'

L.C.R.C. recorded in Liber 5, Page 175

- December 27, 1984

C.I. monument	
28" Maple	N 22.53'
22" Maple	NW 51.69'
40" Oak	SSW 31.59'
PP	S 57.24'

\$ 11.00 CORNER