

SURVEY &
REMONUMENTATION

DEC 01 1998

SECTION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa <small>(County)</small>	Located In: Tallmadge Township	Corner Code ## <u>L-13</u>
1. Public Land Survey	T <u>7N</u> R <u>13W</u>	<u>S 1/4 corner</u>
	T _____ R _____	<u>Sec. 36</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>6N</u> R <u>13W</u>	<u>L-1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

98 JUL 24 PM 1:46

Dan Schultz
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Rodney D. Unema, in a field survey on May 21, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 G.L.O. April 1837 - R. Clark Jr. Set 1/4 Sec. Post @ 40.00 chains 6" W Oak N60°E 25 Links 14" W Oak N57°W 31 Links	No recorded L.C.R.C. Witnesses ; From Ottawa Co. Road Comm. witness map: Iron @ 2652 W. of SE Cor., Sec. 36 Fence E & W Fence N 103' W Fence S 285' E 8" Hickory WSW 16.4' 18" Dbt. Oak W 4'
---	---

*Over for sketch

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13
Found 1/2" Iron Pipe on E-W tree ROW and old fence line
18" Hickory N70°W 16.3'
Double 24" Oak West 4' + to approx ϕ
Measured 2615.98' to SW corner Section 36
Measured 2652.92 feet to SE corner of Section 36
Accepted 1/2" Iron Pipe as a careful and faithful perpetuation of the position of the original corner and replaced with standard Ottawa County Cap on 3/4" X 36" steel bar.

This position checks with the location being held by Medema-VarKooten.

RA. 845 OTTAWA COUNTY
PEER APPROVED 7-20-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Ottawa County Cap on 3/4" X 36" Steel Bar
Corner is on old fence line running E & W and E-W tree ROW
Set nail & O.C. tag in N side 10" Maple S80°E 7.20'
Set nail & O.C. tag in N side 18" Hickory N70°W 16.28'
Set nail & O.C. tag in SE side 24" Double Oak West 5.68'

Corner is common with L-1, T6N, R13W



Signed by Rodney D. Unema Date May 29, 1998
Surveyor's Michigan License No. 33987

SURVEY &
REMONUMENTATION

DEC 01 1998

SECTION

