

SURVEY &
REMONUMENTATION

APR 05 1998 Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
COMMISSIONING Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 DEC 12 PM 4:53

Dorothy M. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R13W</u>	<u>M-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Maurice J. Rosema, in a field survey on March 21, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-4	GLO - 1837 by Noah Brookfield D.S. 10" Hickory at Section cor.	L.C.R.C. recorded in Liber 6, Page 179, Oct. 16, 1991 C.I. mon. Tag in T pole W 24.53' Tag in 20" Maple NW 173.35' Tag in 8" Oak ENE 45.61' Notch in 12" corr culv SW 43.20'	L.C.R.C. recorded as A-4, T7N, R12W Cert. no. 1448 (over) L.C.R.C. recorded as A-4, T7N, R12W Cert. no. 5498 (over)
-----	--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4
Found C.I. mon. in bit. conc. road
Found notch in 12" corr. culvert SW 43.22'
Found nail and K.C. tag in N side 9" Oak ENE 45.57'
Found nail and K.C. tag in E side 21" Maple NNW 173.45'

P.A. 345 OTTAWA COUNTY
DEER APPROVED 12/11/95

Maurice J. Rosema
GOV

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner,

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4
C.I. mon.
X cut in conc. culvert S74°E 31.75'
X cut in conc. culvert S80°W 34.22'
Notch in 12" corr. culvert S45°W 43.22'
Nail and K.C. tag in N side 9" Oak N84°E 45.57'
Nail and K.C. tag in E side 21" Maple N8°W 173.45'
c/l bit. conc. road W 1'



Signed by *Maurice J. Rosema* Date Nov. 20, 1995

Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

L.C.R.C. recorded as cert. no. 5498 (recorded as A-4, T7N, R12W) on June 6, 1980

Standard K.C. mon.

Nail and K.C. tag in N side MBT pole	W 24.51'
Nail and K.C. tag in E side 18" Maple	N10°W 173.42'
X cut in E end conc. culvert	S10°E 136.11'
X cut in W end conc. culvert	S10°W 134.66'
Nail and K.C. tag in N side 6" Elm	N80°E 45.58'
On c/1 N-S gravel road	
On E-W T pole line	

L.C.R.C. recorded as cert. no. 1448 (recorded as A-4, T7N, R12W) on Feb. 4, 1981

Standard K.C. mon.

Nail and K.C. tag in N side MBT pole	W 24.51'
Nail and K.C. tag in E side 18" Maple	N10°W 173.42'
Nail and K.C. tag in SW side 6" Elm	S65°E 58.73'
Nail and K.C. tag in SW side 10" Elm	S30°E 112.11'
X cut in E end conc. culvert	S10°E 136.11'
X cut in W end conc. culvert	S10°W 134.66'