

APR 05 1996

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 DEC 12 PM 4:52

COMMISSION

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T T7N R13W	M-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Deputy Clerk
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Maurice J. Rosema, in a field survey on March 21, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13		
GLO - in 1837 by R. Clark, Jr.	L.C.R.C. recorded in Liber 6, page 83 - Jan. 28, 1991	L.C.R.C. recorded as #5507 - June 6, 1990
16" W. Oak N29°E 34 Lks.	(over)	(over)(rec. as A-13, T7N, R12W)
20" W. Oak S69½°W 70 lks.	L.C.R.C. recorded in Liber 4, Page 292 - Jan. 12, 1982	L.C.R.C. recorded as #1146 - Feb. 4, 1981
	(over)(rec. as M-1, T6N, R13W)	(over)(rec. as A-1, T6N, R12W)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13	
Found C.I. mon. 0.2' below bit. conc. road	
Found nail and K.C. tag in E side T pole	N28°W 67.54'
Found nail and K.C. tag in SE side 17" Hackberry	N35°E 40.97'
Found nail and K.C. tag in W side 18" Hackberry	S10°E 72.20'
Found nail and K.C. tag in W side P pole	S80°W 31.24'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/11/95

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

Murray D. Wedgwood
207

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13	
C.I. mon.	
Found nail and K.C. tag in E side T pole	N28°W 67.54'
Found nail and K.C. tag in SE side 17" Hackberry	N35°E 40.97'
Found nail and K.C. tag in W side 18" Hackberry	S10°E 72.20'
Found nail and K.C. tag in N side P pole	S80°W 31.24'
Center stop sign	N47°E 38.25'
Centerline of bit. conc. road N-S	W 7'
Centerline of bit. conc. road to E	N 10'



Signed by *Maurice J. Rosema* Date Dec. 9, 1995
 Surveyor's Michigan License No. 27459