

SURVEY & REMONUMENTATION

FEB 27 1998

Ottawa County remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 7N R 14W	B-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
97 DEC -8 AM 11:28
Sam Schultz
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

I, Maurice J. Rosema, in a field survey on Jan. 3, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-5	G.L.O. by N. Brookfield in 1832	Set post	10" B Ash	S76°W 20 lks	6" Ash	N 11.03'	12" Elm	N4°E 30 lks	8" Ash	ESE 61.90'	14" Willow	SW 43.30'	16" Willow	NW 35.46'
	L.C.R.C. rec. in Liber 4, Page 1 on Nov. 1, 1979	C.I. monument												
	L.C.R.C. rec. in Liber 4, Page 1 in 1985	C.I. monument (top broken)												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5
Found C.I. monument on centerline of gravel road, top is 0.6' below grade
Found nail in S side 6" Maple clump N86°E 59.35'
Found nail in W side 8" Ash S75°E 61.85'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 9-16-96

YDZ

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5	C.I. monument	
	Set nail and remon tag in S side 6" Maple clump	N86°E 59.35'
	Set nail and remon tag in W side 7" Ash	N3°E 13.36'
	Set nail and remon tag in W side 8" Ash	N75°E 61.85'
	Set nail and remon tag in NW side 15" Willow	S47°W 19.55'
	Set nail and remon tag in SW side 7" Willow	N60°W 27.55'



\$ 1.00 PHOTO

Signed by *Maurice J. Rosema* Date Sept. 16, 1996
Surveyor's Michigan License No. 27459