

# SURVEY & REMONUMENTATION

FEB 27 1998

## Ottawa County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION \_\_\_\_\_

_____	Located in:	Corner Code #
Ottawa (County)		
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	C-2 _____
	T _____ R _____	E 1/4 cor. Sec. 6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Maurice J. Rosema, in a field survey on Jan. 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RECORDED  
97 DEC -8 AM 11:29  
*Dan Schultz*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- |  |   |  |   |
|--|---|--|---|
| C-2<br>GLO - Mullett - 1837<br>post<br>10" Beech -<br>S17°W 25 lks<br>8" Beech -<br>N56°E 11 lks | LCRC per L. 3, P. 134 (1976)<br>conc. mon.<br>14" Pine - S 10.62'<br>16" Maple - N 23.32'<br>12" Pine - NE 25.26' | LCRC per L. 4, P 87 (1980)<br>CI mon.<br>14" Pine - W 10.62"<br>12" Sassafrass - SW 35.50'<br>14" Sassafrass - WSW 42.00'<br>18" Sassafrass - S 40.00' | LCRC per L. 5, P. 219 (1985)<br>CI mon.<br>Nail in E side 18" Oak - N 23.62'<br>Nail in N side 36" Oak - W 18.41'<br>Nail in NE side 10" Pine - SE 14.36' |
|--|---|--|---|

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- LCRC per L 6, P 181 (1991)  
tag cut-off 14" Pine - W 10.60'  
Nail in 14" Pine - W 10.60'  
Nail in 18" Maple - N 23.60'  
Nail in 12" Pine - SE 14.38'

- C-2  
Found CI monument  
Found nail in E side 18" Oak - N 23.65'  
Found nail in SW side 12" Pine - NE 25.30'  
Found nail in NE side 12" Pine - ESE 14.40'  
Found nail in face of 14" stump - W 10.60'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-2  
CI monument  
Set nail and remon. tag in W side 9" tree - S19°W 32.10'  
Set nail and remon. tag in E side 18" Oak - N1°W 23.65"  
Set nail and remon. tag in SW side 12" Pine - N50°E 25.30'  
Set nail and remon. tag in NE side 10" Pine - S59°E 14.40'  
Set nail and remon. tag in E side 14" stump - N86°W 10.60'  
Face wood post - SE 0.8'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12-1-97  
*[Signature]*



\$ 9.00 CORNER  
\$ 1.00 PHOTO

Signed by *Maurice J. Rosema*  
Surveyor's Michigan License No. 27459

Date 12/01/97