

APR 05 1996

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R14W</u>	C-6
	T _____ R _____	(E $\frac{1}{4}$ cor of
	T _____ R _____	Section 18)
	T _____ R _____	Allendale Twp
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

RECORDED

95 NOV 29 PM 1:47

Rhonda Chittman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Maurice J. Rosema, in a field survey on Sept. 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6
 Glo - 1832 (Noah Brookfield D.S.) L.C.R.C. recorded in Liber 5
 10" Beech S46°E 25 lks Page 223 - Aug. 1, 1985 (over)
 10" Beech N57°W 9 lks
 L.C.R.C. recorded in Liber 1
 Page 97 - Oct. 5, 1971 (over)
 L.C.R.C. recorded in Liber 6
 Page 189 - Oct. 23, 1991
 (over)

PA. 345 OTTAWA COUNTY
PEER APPROVED 11-20-95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6
 Found C.I. Monument in monument box.
 Found notch E end conc culvert SW 34.45'
 Found notch W end conc culvert SW 53.85'
 Found Iron on shoulder (bent top) NW 47.67'
 Found Iron on shoulder NE 41.00'

M. J. Rosema



I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6
 C.I. Monument in monument box
 Set nail and Ottawa County remon. tag in W side P pole S0°E 31.85'
 Found notch in top of W end conc culvert S68°W 53.85'
 Found notch in top of E end conc culvert S48°W 34.45'
 Found iron (re-rod) on shoulder N69°E 41.00'
 Found iron (pipe) on shoulder N63°W 47.67'

Signed by *M. J. Rosema*
Surveyor's Michigan License No. 27459

Date October 21, 1995

C-6, T7N, R14W

L.C.R.C. recorded in Liber 1, Page 97

- October 6, 1971

Iron pipe in c/l pavement

E end of culvert SW 34.40'

L.C.R.C. recorded in Liber 5, Page 223

- September 5, 1985

3/4" pipe in monument box

On c/l E-W bit. conc. road

c/l W end conc. culvert WSW 53.80'

c/l E end conc. culvert SW 34.35'

L.C.R.C. recorded in Liber 6, page 189

- November 6, 1991

C.I. Monument

Notch in E end 12" conc. culvert SW 34.46'

Notch in W end 12" conc. culvert SW 53.80'

Iron in shoulder NW 47.40'

Iron in shoulder NE 41.00'

\$ 11.00 CORNER