

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 18 PM 4: 54

Robert D. Callman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	<u>C-8</u>
	T _____ R _____	<u>(W 1/4 cor.</u>
	T _____ R _____	<u>Sec. 20)</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	15	14	13							
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Maurice J. Rosema, in a field survey on Nov. 30, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-8	GLO - 1832 by Britain	LCRC rec. in L. 3, P. 324	LCRC rec. in L. 4, P. 124	LCRC rec. in L. 3, P. 175
10" Beech -	S17°E 17 lks	Iron pipe	P pole - SE 95.67'	3/4" Pipe
8" Beech -	N60°W 15 lks	Fences E and W	c/l 20" Elm Stump - NE 44.00'	P pole - SW 117.72'
				P pole - SE 95.65'
				Fc post - E 26.94'
				Stump - NE 42.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8
 Found C.I. monument (top broken)
 Found nail in NE side P pole - SE 95.68'
 Found nail in W side P pole - SSW 118.12'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 12-9-96

M. J. Rosema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8
 C.I. monument
 On centerline of N-S gravel road, on fence line to W, at road grade
 Nail and remon. tag in N side 6" Elm - N73°W 31.55'
 Nail and remon. tag in N side 12" Pine - S77°E 44.78'
 Nail and remon. tag in N side 6" Elm stump - S62°E 23.60'
 Nail and remon. tag in NE side P pole - S32°E 95.88'
 Nail and remon. tag in W side P pole - S22°W 118.12'



Signed by *M. J. Rosema* Date Dec. 9, 1996
 Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983