

SURVEY & REMONUMENTATION

FEB 27 1998

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Ottawa <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	C-9	
	T <u> </u> R <u> </u>	NW cor. Sec. <u>29</u>	
	T <u> </u> R <u> </u>	_____	
	T <u> </u> R <u> </u>	_____	
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____	
	S <u> </u> T <u> </u> R <u> </u>	_____	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____	
	S <u> </u> T <u> </u> R <u> </u>	_____	

RECORDED

97 DEC -8 AM 11:29

Ray [Signature]
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice J. Rosema, in a field survey on Nov 27, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9		●										
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-9 GLO - Britain 1832 post 30" Elm - N85°W 19 lks 10" Beech - N52°E 14 lks	LCRC per L. 1, P. 671 mon. box	LCRC per L. 5, P. 225 Angle iron in mon. box Nail in NW side 12" Maple - NE 57.88' PK in top of wood post at T box - NW 64.52' PK in top of wood post at T box - SW 55.70' Centerline of E-W B.T. road - S 1' Centerline of gravel road to N - W 6' On centerline of gravel road to S
---	-----------------------------------	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9
Found angle iron in mon. box, replaced iron with 5/8" X 2' steel rod with OC remon. cap
Found PK nail in top of wood post at T box - NW 64.59'
Found PK nail in top of wood post at T box - SW 55.74'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12-1-97
[Signature]

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9
5/8" X 2' steel rod with OC remon. cap in mon. box
Set nail and remon. tag in top of wood post at T box - N33°W 64.59'
Set nail and remon. tag in SW side P pole - N45°W 68.56'
Set nail and remon. tag in SE side 17" Maple - N49°E 58.25'
Set nail and remon. tag in Sw side P pole - S41°E 73.26'
Set nail and remon. tag in top of wood post at T box - S34°W 55.74'
Centerline of E-W bit. conc. road - S 3'
Centerline of gravel road to N - W 6'
On centerline of gravel road to S



\$ 9.00 CORNER
\$ 1.00 PHOTO

Signed by *[Signature]*
Surveyor's Michigan License No. 27459

Date Dec. 1, 1997