

SURVEY & DOCUMENTATION

Ottawa County Remonumentation

RECORDED

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 15 AM 11:51

For corners in **COMMISSION**

Phyllis Callman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Maurice J. Rosema Jan. 2 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-12

GLO - 1832 signed by Noah Brookfield for Calvin Britain D.S.	VanKooten - 1980 per L.C.R.C. Joiner - 1991 per L.C.R.C. rec. in L. 4, P. 91 (over)	L.C.R.C. rec. in L. 6, P. 199 (over)
10" Sugar - N80° E .10 ch.		
10" Beech - N78° W .25 ch.	Rosema - 1988 per L.C.R.C. rec. in L. 5, P. 338 (over)	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12
Found C.I. mon.
Found nail in E. side 36" Ash - N8° W 35.19'
Found nail in S. side 36" Oak - N76° W 29.09'
Found nail in NW. side 18" Oak - S54° W 45.11'
Found nail in S. side 12" tw. Maple - S84° E 47.05'

PA. 345 OTTAWA COUNTY
PEER APPROVED 4/18/94
Bradley D. Nedewold

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12
C.I. mon.
Set nail and remon. tag in E. side 36" Ash - N8° W 35.19'
Set nail and remon. tag in S. side 36" Oak - N26° W 29.09'
Set nail and remon. tag in NW. side 18" Oak - S54° W 45.11'
Set nail and remon. tag in S. side 12" tw. Maple - S84° E 47.05'
Set nail and remon. tag in E. side 15" Oak - S8° E 27.02'
N.-S. fence line - E. 3.2'



Signed by *Maurice J. Rosema* Date Nov. 19, 1994
Surveyor's Michigan License No. 27459

Part A - continued

VanKooten - 1980 per L.C.R.C. rec. in L. 4, P. 91

Iron

Sq. spike in NW. side 14" Oak - SW. 45.11'

Sq. spike in S. side 24" Oak - W. 29.23'

Sq. spike in side 30" Ash - N. 35.24'

Rosema - 1988 per L.C.R.C. rec. in L. 5, P. 338

1/2" iron pipe

Nail in E. side 30" Ash - N. 35.26'

Nail in S. side 30" Oak - WNW. 29.20'

Nail in N. side 18" Oak - SW. 45.11'

Joiner - 1991 per L.C.R.C. rec. in L. 6, P. 199

C.I. mon.

30" Ash - N. 35.26

30" Oak - WNW. 29.20'

18" Oak - SW. 45.11'

12" tw. Maple - E. 47.05'

2005 # 3000
000000
000000
000000
000000