

SURVEY &  
MONUMENTATION

Ottawa County Remonumentation  
 APR 05 1996 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970  
**COMMISSION**

RECORDED

95 DEC 12 PM 4:53

*Phyllis Robinson*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R14W</u>	D-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Maurice J. Rosema, in a field survey on Sept. 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7		●											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 D-7

GLO - 1832 by Noah Brookfield for Calvin Britain D.S. Set post 10" Sugar N16°E 17 lks. 10" Sugar S16°W 15 lks.	L.C.R.C. recorded in Liber 5, Page 223 - Sept. 5, 1985 (over) L.C.R.C. recorded in Liber 1, Page 99 - Oct. 6, 1971 (over)	L.C.R.C. recorded in Liber 2, Page 187 - June 7, 1973 (over)
--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7  
 Found C.I. mon. in mon. box

P.A. 345 OTTAWA COUNTY  
 PEER APPROVED 12/11/95

*Murray D. McDowell*  
 M.D.M.

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7  
 C.I. mon. in mon. box  
 Set nail and O.C. tag in SW side 18" Maple N53°W 61.91'  
 Set nail and O.C. tag in W side 20" Maple N30°W 61.48'  
 Set nail and O.C. tag in NE side 20" Maple N20°W 78.28'  
 Set nail and O.C. tag in top cor. wood fence post S51°W 47.02'  
 Set nail and O.C. tag in N side 36" Maple S72°E 120.96'  
 At centerline X of N-S bit. conc. road and E-W gravel road



Signed by *Maurice J. Rosema* Date October 21, 1995  
 Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 15  
 REVISED MAY 14, 15  
 REVISED JAN., 15

D-7, T7N, R14W

L.C.R.C. recorded in Liber 5, Page 223  
- September 5, 1985

C.I. Mon

Nail in NE side 24" Maple	NW 46.95'
PK in SW side Wood Post at Tele Box	SE 44.38'
PK in NW side Wood Post at Tele Box	SW 45.42'
Nail in S side 24" Maple	WNW 96..06'
At centerline "x" gravel rds E-W and N-S	

L.C.R.C. recorded in Liber 1, Page 99  
- October 6, 1971

C.I. Monument

Cnt. Street sign	SE 50.42'
Nail in face of P.Pole	SE 33.64'
Nail in face of 28" Maple	NW 45.75'
Nail in face of 38" Maple	ESE 119.58'
Nail in face of 24" Maple	WNW 77.62'
Nail in face of 3" Pine	NE 60.67'
Nail in face of 5" Pine	SE 108.15'
Nail in face of 5" Pine	SSW 85.53'

L.C.R.C. recorded in Liber, 2 Page 187  
- June 7, 1973

Monument Box

PK in side of P.Pole	SE 34.03'
PK in side of P.Pole	NE 42.36'
Nail in SE side 16" Maple	NW 45.76'