

**SURVEY &  
REMONUMENTATION**

Ottawa County Remonumentation

**RECORDED**

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 15 AM 11:51

For corners **COMMISSION**

*Stephen B. Williams*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Ottawa (County) Located in: Corner Code #

1. Public Land Survey	T <u>7N</u> R <u>14W</u>	<u>D-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Maurice J.  
Rosema

Jan. 2 94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

D-13  
GLO - 1837 by Joiner - 1980 per Milliron - 1991 per  
Loucius Lyon D.S. L.C.R.C. rec. in L.C.R.C. rec. in  
12" Hemlock - N44°E .36 ch. L. 4, P. 136 L. 6, P. 150  
10" Sugar - N76°W .25 ch. (over) (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13  
Found C.I. mon. in mon. box  
C.I. mon. - W. 22.45'  
Nail in SE. side P. pole - N61°E 48.84'  
P.K. nail in SW. side P. pole - N38°W 104.70'  
P.K. nail in SW. side T. post - N45°W 57.80'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position:

D-13  
C.I. mon. in mon. box  
Centerline of street sign - N40°W 51.17'  
Nail and remon. tag in SE. side P. pole - N61°E 48.84'  
Nail and remon. tag in SW. side P. pole - N38°W 105.70'  
Nail and remon. tag in SW. side T. post - N45°W 57.80'  
On centerline of N.-S. gravel road  
On centerline of E.-W. bit. conc. road

45 OTTAWA COUNTY

PLAN APPROVED

4/18/94

*Robert P. Hedwood*



Signed by \_\_\_\_\_

Date \_\_\_\_\_

April 18, 1994

Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 197  
REVISED MAY 14, 197  
REVISED JAN., 198

Part A - continued

Joiner - 1980 per L.C.R.C. rec. in L. 4, P. 136

C.I. mon.

P. pole - NE. 49.01'

Tele. pole - NW. 57.89'

Street sign - S. 15.13'

Cor. fence post - SW. 26.93'

Blendon cor. - W. 22.50'

Milliron - 1991 per L.C.R.C. rec. in L. 6, P. 150

C.I. mon.

P.K. nail in SW. side 6" post - N55°W 57.76'

P.K. nail in SW. side P. pole - N30°W 104.67'

1/2" rebar on W. side gravel road - N5°W 98.55'

1/2" rebar at NE. cor. intersection N35°E 108.05'

16-d nail in SE. side P. pole - N55°E 48.96'

P.K. nail in E. side 4" post - S40°W 35.22'

Blendon cor. - N90°W 22.50'

RECORDED  
INDEXED  
SERIAL #  
DATE #

120  
9.00  
150  
00