

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 18 PM 4:54

R. J. Rosema
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T7N R 14W	E-10
	T R	(W ¹ / ₂ cor.,
	T R	Sec. 28)
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Maurice J. Rosema in a field survey on Dec. 6, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-10

GLO - 1832 by Britain
 Post
 10" Elm - N37°W 43 lks
 10" W Ash - S27°E 15 lks

Information per the files of
 Nederveld Associates
 N and J capped iron
 Nail and tag in E side 10"
 Oak - S 12.88'
 Nail and tag in E side 18"
 Maple Clump - N 20.06'
 Nail and tag in NE side 8" Ash
 - S 7.15'

Information from the files of Tru-
 Line Surveying P.C.
 Capped rerod
 Nail in E side 8" Oak - S 12.86'
 Nail in NE side 6" Ash - SE 7.08'
 Nail in E side 18" Maple - N 20.06'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10

Found 1/2" rerod, replaced with 5/8" x 3' steel rod with remon. cap
 Found nail in E side 10" Oak - S 12.82'
 Found nail in E side 36" Maple clump - N 20.09'
 Found nail in NE side 6" Ash clump - SE 7.10'

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 12-9-96

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

M. J. Rosema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10

5/8" x 3' steel rod with remon. cap
 Set nail and remon. tag in E side 36" Maple clump - N5°W 20.10'
 Set nail and remon. tag in NE side 6" Ash clump - S60°E 7.10'
 Set nail and remon. tag in S side 10" Oak - S4°W 12.82'
 Set nail and remon. tag in W side wood post - S0°E 0.75'
 Set nail and remon. tag in S side 22" Oak - N85°W 37.10'
 Centerline of N-S ditch - W 11'±



Signed by Maurice J. Rosema Date Dec. 9, 1996
 Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 197
 REVISED MAY 14, 197
 REVISED JAN., 198