

APR 05 1996 Ottawa County Remonumentation

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 DEC 12 PM 4: 50

*R. J. ...*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T T7N R14W	F-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5			●										
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Maurice J. Rosema, in a field survey on Jan. 19, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-5  
GLO - 1832 by Naoh Brookfield L.C.R.C. recorded in Liber 1,  
for Calvin Britain D.S. Page 527 - June 9, 1972  
Set post C.I. mon.  
24" W. Ash N73°W 12 lks. X in N end culvert NW 77.46'  
20" Hemlock S52°E 50 lks. X in S end culvert WNW 65.57'  
Street sign NNE 33.93'  
Nail in face of 6" cluster Oak E 113.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5  
Found C.I. mon. in mon. box  
All wit. are gone but this location checks with prev. Tru-line Surveying P.C. field data.

P.A. 345 OTTAWA COUNTY


PEER APPROVED 12/11/95

*M. D. ...*

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5  
C.I. mon. in mon. box  
Set nail and O.C. tag in N side wood post S84°E 48.00'  
Set nail and O.C. tag in N side wood post S90°E 34.21'  
Set nail and O.C. tag in top of wood fence post N26°W 73.05'  
Set nail and O.C. tag in N side wood post N86°W 40.74'  
c/1 N-S bit. conc. road W 1'  
c/1 gravel road to W N 29'



Signed by *Maurice J. Rosema*  
Surveyor's Michigan License No. 27459

Date October 21, 1995