

SURVEY & REMONUMENTATION

APR 24 1995

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:48

COMMISSION

For corners in

Phyllis R. Hollman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	<u>G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Maurice J. Rosema, in a field survey on Oct. 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-5	Englert - 1973 per L.C.R.C. Joiner - 1981 per L.C.R.C.	Rosema - 1984 per L.C.R.C.
	rec. in L. 2, P. 419	rec. in L. 5, P. 146
	1" steel bar	C.I. mon.
	Cor. f.p. - WSW. 23.64'	6" Poplar - NE. 36.90'
	Culvert p. - SE. 15.82'	4" Cherry - ENE. 36.80'
	8" Aspen - NW. 35.79'	X in culv. - W. 12.68'
		3/4" rerod - E. 12.22'
		Nail in SE. side 6" Poplar - NE. 50.90'
		X in top conc. culv. - W. 12.63'
		3/4" rerod - E. 12.18'
		c/l N.-S. gravel road - E. 3'
		Nail in S. side 4" Cherry - ENE. 36.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5	G.L.O. - 1832 signed by Noah Brookfield for Calvin Britain D.S.
C.I. mon.	10" Hemlock - N1°W .36 ch.
Found nail in 4" Cherry - ENE. 36.80'	10" Maple - N79°E .23 ch.
Found nail in 12" Poplar - NE. 50.84'	
X in culv. - W. 12.65'	

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 12/12/94
Maurice J. Rosema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5
 C.I. mon.
 Set nail and remon. tag in S. side of 4" Cherry - N78°E 36.80'
 Set nail and remon. tag in SE. side 12" Poplar - N43°E 50.84'
 Set nail and remon. tag in N. side 5" Apple - S41°E 39.79'
 Set nail in culvert - N84°W 12.65'



Signed by *Maurice J. Rosema* Date Nov. 19, 1994
 Surveyor's Michigan License No. 27459