

# SURVEY & REMONUMENTATION

APR 25 1995

Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:31

COMMISSION

*D. J. ...*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

For corners in Ottawa (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	<u>G-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Maurice J. Rosema, in a field survey on Oct. 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1. Rosema - 1981 per L.C.R.C. rec. in L. 4, P. 155 2" rerod Nail in E. side 3" Elm - N. 16.48' Nail in S. side 12" Maple - WSW. 13.64' Nail in N. side 20" Maple - WSW. 17.15' c/l ditch to W. and on N.-S. brush line	Rosema - 1985 per L.C.R.C. rec. in L. 5, P. 222 Capped Exxel rerod Nail in E. side 3" Elm - N. 16.41' Nail in S. side 15" Maple - WNW. 13.65' Nail in N. side 20" Maple - WSW. 17.14' On centerline ditch to W. and on N.-S. brush row
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1. C.I. mon. and nail in N. side 22" Maple WSW. 17.07' and nail in S. side 16" Maple - WNW. 13.60' and nail in 12" tri. stump - N. 35.23' and nail in 12" stump - WSW 33.18'	Joiner - 1991 per L.C.R.C. rec. in L. 6, P. 196 C.I. mon. 22" tw. Maple - WSW. 17.13' 16" Maple - WNW. 13.59' 12" tri. Ash - N. 35.30' 12" Ash - WSW. 33.18'	G.L.O. - 1832 signed by Noah Brookfield for Calvin Britain D.S. Set 1/2 mile post 18" Maple - S35°W .10 ch. 18" Elm - N85°E .20 ch.
--	---	--

do hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1. C.I. mon.  
at nail and remon. tag in N. side 22" Maple - S80°W 17.07'  
at nail and remon. tag in S. side 16" Maple - S82°W 13.60'  
at nail and remon. tag in SW. side 12" tri. stump - N3°E 35.23'  
at nail and remon. tag in N. side 12" stump - S82°W 33.18'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

*Murray D. Hedewell*



Signed by Maurice J. Rosema Date November 19, 1994  
 Surveyor's Michigan License No. 27459