

SURVEY & REMONUMENTATION

Ottawa County Remonumentation

RECORDED

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 15 AM 11:52

For corner(s) **COMMISSION**

Dorothy Holloman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Maurice J.

Rosema

Oct. 20 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9

GLO - 1832 by Hooth - 1980 per L.C.R.C. Rosema - 1985 per L.C.R.C.
Noah Brookfield for rec. in L. 4, P. 116 rec. in L. 5, P. 221
Calvin Britain D.S. (over) (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9

Found 1" rod in mon. box, replaced with 3/4" x 2" steel rod with standard remon. cap
Found nail in W. side tw. 18" W. Cherry - S1°W 61.02'
Found P.K. nail in top of wood post - S37°E 61.11'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Harold D. Wedemeyer

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9

3/4" x 2" steel rod with standard remon. cap
Set nail and remon. tag in W. side tw. 18" W. Cherry - S1°W 61.02'
Set nail and remon. tag in top of wood fence post - S37°E 61.11'
Set nail and remon. tag in W. side 10" Ash - N14°E 60.90'
Set nail and remon. tag in E. side 17" Ash - N4°E 106.50'
Set nail and remon. tag in SE. side Power pole - N67°W 147.00'



Signed by *Maurice J. Rosema* Date _____
Surveyor's Michigan License No. 27459

Dec. 10, 1994

Part A - continued

Hooth - 1980 per L.C.R.C. rec. in L. 4, P. 116

3/4" iron in mon. box

Tele. pole - S60 W 84.41'

24" Cherry - S. 61.00'

Chisled arrow on SE. side of MH. rim - N70 W 113.03'

Tele. pole (RLS cap 21272) - S47 E 68.62'

Rosema - 1985 per L.C.R.C. rec. in L. 5, P. 221

1/2" iron in mon. box

Nail in W. side tw. 18" W. Cherry - S. 60.99'

Chisled on SE. side of Manhold rim - NW. 113.10'

Centerline of cor. steel fence post - N. 75.19'

P.K. nail in SE. side Power pole - ENE. 152.81'

Centerline of E.-W. road - S. 2.2'

P.K. nail in tip of fence post - SE. 61.06'

0000 #
0000 #
0000 #
0000 #
0000 #