

**SURVEY & REMONUMENTATION**

Ottawa County Remonumentation

**RECORDED**

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**

94 DEC 15 AM 11:53

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

*Robert C. Williams*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Maurice J.  
Rosema

Dec. 7 94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
G-13

GLO - (no date) by Schiele - 1979 per L.C.R.C. Britnall - 1991 per L.C.R.C.  
Loucius Lyon D.S. rec. in L. 3, P. 366 (over) rec. in L. 6, P. 154 (over)  
16" Hemlock - N83 E .45 ch.  
8" Walnut - N 50 1/2 W .28 ch. Joiner - 1981 per L.C.R.C.  
rec. in L. 4, P. 194 (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13  
Found C.I. mon. in mon. box  
Found P.K. nail in E. side Power pole - N38° W 136.87'  
Found nail in W. side 10" Aspen - N10° E 145.48'  
Found C.I. mon. in mon. box - N90° W 49.49'

PA. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

*Robert D. Nedewell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13  
C.I. mon. in mon. box  
Set nail and remon. tag in top of conc. curb - S2° E 28.16'  
Set P.K. nail and remon. tag in top of conc. curb - S70° W 79.58'  
Set nail and remon. tag in e. side Power pole - N38° W 136.87'  
C.I. mon. in mon. box - N90° W 49.49'  
Set nail and remon. tag in E. side 12" Maple - N10° W 184.08'  
Set nail and remon. tag in W. side 10" Aspen - N10° E 145.48'



Signed by *Maurice J. Rosema* Date Dec. 10, 1994  
Surveyor's Michigan License No. 27459

Part A - continued

Schiele - 1979 per L.C.R.C. rec. in L. 3, P. 366

1 1/4" iron

Tele. pole - WSW. 84.93'

Power pole - WSW. 138.82'

Power pole - NW. 136.92'

Blendon cor. - W. 49.44'

Joiner - 1981 per L.C.R.C. rec. in L. 4, P. 194

C.I. mon.

Tele. pole - SW. 84.93'

Blendon cor. - W. 49.46'

Street sign - NW. 51.71'

Stop sign - SW. 33.48'

Brintnall - 1991 per L.C.R.C. rec. in L. 6, P. 154

16D in W. side 8" Poplar - N10°E 145.41'

P.K. nail in NE. side Power pole - N35°W 136.30'

P.K. nail in c/l in top conc. curb - S. 28.43'

P.K. nail in c/l top curb - S70°W 79.40'

P.K. nail in N. side Power pole - S75°W 140.25'

Sec. cor. - W. 49.47'

CODE # 120 N  
OWNER 7.00  
CODE # 150 N  
OWNER 2.00