

**SURVEY &  
REMONUMENTATION**

Ottawa County Remonumentation  
**APR 05 1996 LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 DEC 12 PM 4:52

*D. J. Rosema*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

For corners in

**COMMISSION**

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R14W</u>	<u>H-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Maurice J. Rosema in a field survey on Dec. 28, 1994  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-5	GLO - 1832 by Noah Brookfield for Calvin Britain D.S.	L.C.R.C. recorded in Liber 4, Page 277 - Dec. 31, 1981	L.C.R.C. recorded in Liber 5, Page 224 - Aug. 1, 1985
	Set post	Steel bar	3/4" steel bar
	20" Beech S 24 lks.	X cut in E end conc. culv.	X cut in E end conc culv. NE 69.55'
	10" Hemlock N3°E 45 lks.	X cut in S end conc. culv.	SE 53.75'
		Street sign	WNW 22.43'
		Power pole	NW 167.72'
		c/l asphalt	E 0.3'
			X cut in S end conc culv. SE 53.78'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found C.I. mon. in mon. box  
 On centerline of N-S bit. conc. road  
 and on centerline of bit. conc. road to E  
 c/l st sign WNW 22.41'  
 c/l st sign SE 51.30  
 At c/l X of roads

PA. 345 OTTAWA COUNTY

PEER APPROVED 12/11/95

*Kudoy P. Nedewald*  
*NDJ*

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5	C.I. mon. in mon. box	
	Set nail and O.C. tag in S side wood sign post	N63°E 74.26'
	Set nail and O.C. tag in W side P pole	N11°W 167.96'
	Set nail and O.C. tag in S side 3" Maple	S87°W 59.02'
	Set nail and O.C. tag in W side P pole	S15°W 253.08'
	Found X cut in top of culvert	N61°E 59.82'
	Found X cut in top of culvert	S59°E 57.07'



Signed by *Maurice J. Rosema*  
 Surveyor's Michigan License No. 27459

Date November 20, 1995