

FEB 24 2000

RECORDED

99 OCT 27 PM 1:50

Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Ottawa

(County)

Located In:

Corner Code #

1. Public Land Survey

T 7NR 14W

H-9

T R

N 1/4 corner, Section 27

T R

Allendale Township

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Gary P. Rosema*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Maurice J. Rosema, in a field survey on August 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-9  
 GLO - 1832 LCRC per Liber 5, Page 551  
 Britain D.S. (Rosema - 1984)  
 Set post (over)  
 12" Sugar - N13°W  
 22 links LCRC per Liber 3, Page 310  
 12" Lymm. - S38°E (Campbell - 1978)  
 23 links (over)

LCRC per Liber 2, Page 295  
(Bonnema - 1973)  
(over)

LCRC per Liber 1, Page 511  
(Roon - 1972)  
(over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


H-9  
Found 1/2" re-rod in monument box, replaced iron rod with 3/4" x 2' steel rod with remonumentation cap  
SE. corner (new brick face) of building - N50°W 100.50'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9  
 3/4" x 2' steel rod with remonumentation cap in monument box  
 Set nail and remonumentation tag in E. side Power pole - N27°E 58.02'  
 Set nail and remonumentation tag in E. side Power pole - S33°W 62.62'  
 Set nail and remonumentation tag in N.-S. conc. sidewalk - S15°E 89.49'  
 Center of top of hydrant - N52°W 55.34'  
 SW. building corner - N48°E 152.76'  
 SE. corner brick building - N50°W 100.50'

9/13/99  
*GDR*



Signed by *Maurice J. Rosema*  
Surveyor's Michigan License No. 27459

Date September 11, 1999

FEB 24 2000

**SECTION**

LCRC per Liber 1, Page 511  
(Roon - 1972)

No point in place

Corner is 0.17' S of 0.78' E. of center of monument box

NW. corner of store - SE. 48.00'

NE. corner of station - SW. 59.12'

SW. corner of conc. sign base - NE. 49.42'

LCRC per Liber 2, Page 295

(Bonnema - 1973)

1/2" iron

NW. corner of block building - SE. 48.60'

NE. corner gas station - SW. 58.49'

Nail in side P. pole - NNE. 58.52'

LCRC per Liber 3, Page 310

(Campbell - 1978)

3/8" re-rod

NW. corner brick building - S42°E 48.62'

NE. corner nearest building - S37°W 58.55'

SE. building corner - N49°W 99.93'

Power pole - N29°E 58.50'

LCRC per Liber 5, Page 151

(Rosema - 1984)

1/2" re-rod in mon. box

top of SW. bolt at base of sign - NE. 51.80'

NE. corner brick gas station - SW. 58.72'

SE. corner casting of catch basin - NNW. 53.24'